

The Journal of the **INSTITUTE OF METALS**

and
METALLURGICAL ABSTRACTS



In this Issue :

	PAGE
1114. A Study of Process Variables in the Production of Aluminium Powder by Atomization. <i>J. S. Thompson</i>	101
1115. The Surface Tension and Density of Lead-Antimony and Cadmium-Antimony Alloys. <i>H. T. Greenaway</i>	133
1116. 1947 Autumn Lecture: The Metallurgical Resources of Scotland. <i>G. Wesley Austin</i> .	149

NOVEMBER 1947

EFCO-VIRGO DESCALING PROCES

for STEEL and ALLOY STEELS

*Why not spend less money—do less work
for better results and more production*

LESS WORK

The process is very simple. The equipment required is a salt bath, water quench tank and bright dip tank (weak acid).

Scale breaking and sandblasting is eliminated and there is no auxiliary equipment to be operated.

LESS MONEY

Base metal loss is practically eliminated. Acid consumption is low and the space required for the plant compared with ordinary pickling is much less.

BETTER RESULTS

The work has a superior surface finish—unetched and bright. There is no pitting or other dimensional losses.

MORE PRODUCTION Faster pickling cycles—minutes instead of hours.
There is less handling.

★ Send for more detailed information regarding the equipment and how to adapt existing pickling equipment to the EFCO-VIRGO Process.

ELECTRIC RESISTANCE FURNACE CO. LTD.

Associated Companies:—ELECTRIC FURNACE Co. Ltd., ELECTRO-CHEMICAL ENGINEERING Co. Ltd.

NETHERBY, QUEENS ROAD,
Telephone: Weybridge 3816




WEYBRIDGE, SURREY
Telegrams: Resistafur, Weybridge

Your electrodeposition problem

is our business to offer you a free and un-
used source of advice and assistance wherever
Nickel and its alloys may be used with ad-
vantage. We maintain one of the finest research
laboratories in the country and our in-
formation services are second to none. Our
technical staff are always willing to make
personal calls to share their knowledge with
you. Take advantage of this service: we
can draw on a wealth of
experience—on your behalf.

**may be
no problem
to us**




*A finger on
the world's metallurgical pulse*

THE MOND NICKEL COMPANY LTD

Grosvenor House, Park Lane, London, W.1

9/M/1



**This needs
looking into**

By means of radiography you can look into the heart of castings, welds and assemblies . . . detect flaws that might otherwise remain hidden.

Radiography is also a design tool. Safeguarded by the X-ray test, designers can use less metal with equal safety — achieve better design with economy in material.

CAN INDUSTRIAL RADIOGRAPHY HELP YOU?

A booklet with this title, outlining some of the industrial applications of radiography, will be sent free on request to

KODAK Ltd.

DEPT. 539, KODAK HOUSE, KINGSWAY, LONDON, W.C.2

From. B.E.H.
To. man. Dir.

Memo. Ref. 124/P.5/47.

Continued.

7 7.47

decided, unanimously, that the best, if not the only way to keep pace with the new production schedule is to use pressure die castings.

Agreed
What
Alloy
shall we
specify?
M.D.

9.7.47

B.E.H.

I was

not asking

for an

advertisement

for this

Alloy!

M.D.

Mazak. This zinc alloy conforms to B.S. 1004. It has the tensile strength and hardness essential for casting thin sections, thereby saving metal. Its appearance as cast is excellent, it needs little or no final machining and because of its fluidity at moderate casting temperatures, intricate components and even threads can be cast.

Agreed M.D.

MAZAK

FOR PRESSURE DIE-CASTING


km

ALLOY

FOR FORMING AND BLANKING DIES

IMPERIAL SMELTING CORPORATION LIMITED

37 DOVER STREET, LONDON, W.1



'I didn't know'

EDGAR ALLEN'S *made*

STEEL CASTINGS
TOOL STEELS
PERMANENT MAGNETS
CUTTING TOOLS
(Carbide, Butt-Welded, etc.)
STAINLESS and HEAT-RESISTING STEELS
MINING-DRILL STEELS
ALLOY CONSTRUCTIONAL STEELS
CRUSHING and GRINDING MACHINERY
CEMENT-MAKING PLANTS
ROTARY KILNS and DRYERS
COMPLETE GRAVEL PLANTS



*Which of these
statements
applies to you?*

We do. But we make so many things that in these days of paper shortage we can't advertise all of them all the time. So people forget. This advertisement is a reminder, and if you want still more detail of what we make, write for our guide to **EDGAR ALLEN PRODUCTS** to

Our representatives frequently find themselves confronted with one or other. It isn't that we don't make our products known

EDGAR ALLEN & CO, LIMITED
IMPERIAL STEEL WORKS:- SHEFFIELD.9

Why Hind ?

- Constant Quality and Speedy Service—Home or Export
- Boosts Export Orders
- Hastens Home Production
- The Backbone of Iron, Steel or Alloy Products

Hind Metal Ingots meet your needs for anything and everything in metal. Hind Metal is always up to standard specification and in all cases where Refined Iron, Gun Metal, Non-ferrous or Aluminium Alloy Ingots are called for, Hind supply the right grade at the right time—just when you want it—whether in Great Britain or Overseas. In Yorkshire, Lancashire, Birmingham or London areas we deliver within 24 hours. Consult us on your production problems—we can supply the answer for home or export.



Hind Metal



REFINED IRON, GUN METAL, NON-FERROUS AND ALUMINIUM ALLOY INGOTS

E. HIND (SOUTH BANK) LTD., SOUTH BANK-ON-TEES, YORKSHIRE

COPPER'S CONTRIBUTION



1450 B.C. Casting of copper and its alloys has been practised for at least 5000 years. A painting of about 1450 B.C. which depicts the casting of copper doors for the Temple at Karnak still exists.



1540 At about this time, heavy copper wire was drawn by water power, the operator sitting in a swinging seat and gripping the wire with his tongs every time they were returned by the revolving crank.



1700 Power-driven copper and brass rolling mills were introduced into Britain at about the end of the 17th century, and the old method of producing strip and sheet by battery was slowly superseded.



1947 An uninterrupted flow of copper from the molten phase to the end-product was for long a dream of inventors. Now, semi-fabricated forms are being produced on a commercial scale, by continuous casting.



1950 In metallurgical progress, copper will play as full a part in the future as it has played in the past. It may help to solve your own problems. The services of the Copper Development Association are at your

disposal. Write to Kendals Hall, Radlett, Herts. (Radlett 5616)




COPPER DEVELOPMENT ASSOCIATION

Aluminium makes progress economical


How

Reminiscent of a Roman chariot, this type of pony milk float was first used in 1880. Its carrying capacity was two 17-gallon churns.



became . . .

A present-day milk delivery van used by The Midland Counties Dairy Ltd., Birmingham — light, speedy and hygienic. The body is built of Noral aluminium alloy and weighs only 4 cwt. 63 lbs.



Progress in design has gone hand in hand with the development of light metals. Especially is this noticeable in the field of transport, where aluminium has long contributed to the solution of a great many vital problems—problems of weight, strength, corrosion, fabrication, performance and maintenance.


For, whatever the problem, aluminium emerges as the grand co-ordinating medium possessing those unique properties necessary to give substance to new ideas. What greater spur could the creative mind desire?

ALUMINIUM UNION LIMITED

The largest distributors of Aluminium and its Alloys in the British Empire

THE ADELPHI, STRAND, LONDON, W.C.2

— An ALUMINIUM LIMITED Company —



MULLARD - B.T.L. POTENTIOMETRIC TITRATION APPARATUS

An entirely new instrument for potentiometric titrations, an outstanding feature of which is the incorporation of an electron beam indicator as an indicating device in place of a needle galvanometer.

The components are :

TITRATION UNIT comprises a heavy cast iron stand fitted with two burettes, electrode holders, automatic stirring, hot plate, and "Magic Eye" balance indicator.

POTENTIOMETER UNIT. A potentiometer operating from A.C. mains with a range from 0 to 1600 mv., sensitive to 2 mv. Also provided with sensitivity switch, polarising current switch, and a cathode ray tube indicator.


ELECTRODES. Five interchangeable electrodes, e.g., two platinum, and one each tungsten, calomel, and hydrogen, permitting the use of various electrode combinations.

★ *The apparatus may be used for all types of oxidation-reduction and acid-alkali titrations, and in a limited manner for certain pH determinations.*

BAIRD & TATLOCK (LONDON) LTD.

Scientific Instrument Makers

14-17 ST. CROSS STREET, LONDON, E.C.1



*A word about
RADIOLOGICAL
examination...*

...and "X-ray quality" castings




The fluorescent method of crack detection, involving the impregnation of the castings with a fluorescent material and their subsequent examination in ultra violet light, constitutes a useful supplement to X-ray inspection. The application of this method to a light alloy casting is shown above.

The radiological examination of castings, originally developed to meet the requirements of the aircraft industry for highly-stressed light alloy components, has long since been established on a routine basis. Our own very completely equipped radiological department has been in operation for more than ten years . . . Other industries have now come to recognise the value of this penetrating supplementary inspection service and, by specifying "X-ray quality", have been able with advantage to extend their use of non-ferrous castings and reap the full advantage of light alloys in their designs . . . Substantial savings can also be made by the radiological examination of castings calling for a considerable amount of machining: hidden faults are discoverable *before* the casting reaches the machine shop—not on the last operation.

J. STONE
& COMPANY LIMITED

WIMBORNE & CHARLTON. London Offices: OCEANIC HOUSE, 1a COCKSPUR STREET, LONDON, S.W.1.



McKECHNIE *metal technique*

ensures uniform composition of metal, metallurgically controlled to exacting standards, supplied in the most convenient form. The McKechnie range of non-ferrous ingots covers the needs of the foundry, and conforms to B.S.I. requirements. Gunmetal—Phosphor Bronze—Aluminium Bronze—Manganese Bronze—Brass—Antifriction Metal.

McKECHNIE BROTHERS LTD., Rotton Park Street, Birmingham, 16 Phone: Edgbaston 3581 (7 lines)

Branches: LONDON—62 Brook Street, W.1. Phone: Mayfair 6182/3/4. LEEDS—Prudential Buildings, Park Row. Phone: Leeds 23044. MANCHESTER—509/513 Corn Exchange Buildings, 4. Phone: Blackfriars 5094. NEWCASTLE-ON-TYNE—90 Pilgrim Street. Phone: Newcastle 22718.



*Bolton's Copper
for Industry*



Bolton's Copper Products comply with all relevant British Standard specifications and many other Home, Colonial and Foreign Govt. requirements.

Thomas Bolton & Sons Ltd. manufacture Copper and Copper Alloys in the form of Wire, Strand, Sheet, Strip, Plates, Bars, Rods, Tubes, Sections, Machined Parts, etc.

Write for Bolton Publication No. 10

THOMAS BOLTON & SONS LTD. Estab. 1743

HEAD OFFICE: WIDNES, LANCs. TELEPHONE WIDNES 242
London: 168, Regent Street, W.1. Telephone Regent 6427/9

CVS-101

ELEKTRON

adds

LIGHTNESS

and welds

as easily

as steel

or aluminium

Welded tubular chair, made in ELEKTRON AM. 503 Sheet Material, with riveted seat.

ELEKTRON is welded by standard oxy-acetylene equipment and the technique employed is similar to that adopted for aluminium alloys, although special fluxes and welding rods (readily obtainable) should be used. Due to its comparatively low melting point, latent heat of fusion and low specific gravity, a small amount of heat required to weld ELEKTRON is less than with most other metals that are welded. On the other hand, the fact that the thermal conductivity of ELEKTRON is lower than that of aluminium means that heat is concentrated under the welding flame and welding can be carried out more rapidly.

The latest technique is Argonarc Welding, in which Argon—an inert gas—is passed through the torch and acts as a shroud to protect the welds from contamination by atmospheric oxygen and nitrogen. Argonarc welding overcomes the fear of corrosive after-effects, as no fluxes are used.

CHANGING TO ELEKTRON

Your first step is to consult F. A. Hughes & Company Ltd., who can help you with further information. There's not a lot of difference between the handling of ELEKTRON and that of other lightweight alloys, but there is a tremendous improvement in the results you obtain once you change to ELEKTRON. Write to Metals Department.

A. HUGHES & CO. LTD · ABBEY HOUSE · LONDON N.W.1

L11323C



PIPE COUPLINGS

ELECTRICALLY HEATED PRESSURE HEADS

CONTINUOUS FILM RECORDING CAMERAS

AND EQUIPMENT FOR CATHODE RAY

OSCILLOGRAPHY, ETC.



We undertake the Design, Development and Manufacture of any type of Optical — Mechanical — Electrical Instrument. Including Cameras for special purposes.

Avimo Limited, Taunton, England · Telephone Taunton 3



..Bristol Fashion



The site of Bedminster Smelting Works from a print dated 1734.



TODAY Capper Pass are all ship-shape and carrying on their production of Tin Alloys for solder manufacture; 99.99 per cent. Pure Tin suitable for alloys, collapsible tubes, pure Tin coatings, Tin oxide and other specialised Tin products; and Pig Lead.

THEY require as raw materials all grades of Tin Ores and Tin and Lead bearing Residues, Slags, Ashes and Drosses and will welcome offers from any part of the World. They specialize in treating exceptionally complex and low grade materials.

CAPPER PASS & SON LTD.
Bedminster Smelting Works, Bristol

Continuous Production Heat Treatment in *controlled atmosphere*



installa-
ns throughout
e world are daily
oving the reliability,
onomy and consistent
h performance of Birlec
esh belt conveyor furnaces
continuous, arduous produc-
n heat treatment.

1. Close-mesh conveyor belt handles parts of widely varying shapes and sizes.
2. Patented self-compensating drive maintains minimum belt stress and maximum belt life.
3. Flexible belt-speed control permits correct treatment of varying types of work.
4. Standardised furnace sizes from 25 to 1,500 lb. per hour production capacity.
5. Standardised generators for all types of non-oxidising atmosphere.



BIRLEC LTD., TYBURN RD., ERDINGTON, BIRMINGHAM 24

LEWIS'S

Telephone :
EUSon 4282
(5 lines)

SCIENTIFIC BOOKS

Select stock of books
on METALLURGY and
ALLIED SUBJECTS

Please state interests when writing

LEWIS LENDING LIBRARY

Scientific and Technical

ANNUAL SUBSCRIPTION from:
ONE GUINEA

Prospectus post free on application

H. K. LEWIS & Co. Ltd.

LONDON : 136, GOWER STREET

"ANALOID" (Reg'd.)

system of

RAPID ANALYSIS

(Metallurgical)

NEW DESCRIPTIVE BOOKLET

No. 336.

Entirely re-written, giving
several new methods and
many improvements in exist-
ing "Analoid" methods.

*Sent post free on
request to*

RIDSDALE & CO., LTD.

Metallurgical Chemists

234 Marton Road,
MIDDLESBROUGH

SOZOL

**POSITIVELY PREVENTS
THE FORMATION
OF RUST
AND CORROSION**

*The experience of
30 years in the field
of Rust Prevention
is at your service*

SOZOL (1924) LTD. 2 Copthall Buildings
LONDON, E.C.1

BUREAU OF ANALYSED SAMPLES, LTD.

New Standard Samples:

B.C.S. No. 233

Permanent Magnet Alloy
11% Ni, 7% Al, 5% Cu, 24% Co.

B.C.S. No. 230 Cast Steel

0.007% N, 0.14% Ni, 0.46% Cr,
0.17% Mo, 0.085% Cu.

B.C.S. No. 229, 0.6% Silicon
Steel 0.59% Si.

Send for latest list No. 337 showing
15 carbon steels, 11 alloy steels,
7 cast irons, 7 ferro alloys, 9 non-
ferrous alloys, 2 ores and 8 pure
reagents and metals to 234 Marton
Road, Middlesbrough.

DURALUMIN

REGD TRADE MARK

Strength & Lightness

A web of silk and a metal, both a source of wonder to many, and having this in common — lightness and great strength. "DURALUMIN" the light metal alloy—a third the weight of steel yet as strong, easy to work and in ample supply—has proved its worth to British industry in a great variety of ways. Our wide experience is gladly at your service; write to :—



JAMES BOOTH & COMPANY LIMITED, BIRMINGHAM, 7

ELECTRONIC
CONTROL



HIGH ACCURACY

RESISTANCE THERMOMETER CONTROLLER

FOR CREEP
TESTS, ETC.

This is a purely electronic controller giving an output proportional to the deviation of the temperature from the desired value. It operates up to 800° C. with a platinum resistance-thermometer. Sensitivity one part in 5000. Primarily developed to control the tem-

perature of creep test specimens, the SUNVIC RESISTANCE THERMOMETER CONTROLLER is suitable for high accuracy work within the range covered by platinum and nickel resistance thermometers. For details, please request technical publication RT 10/50.

SUNVIC CONTROLS LTD., Stanhope House, Kean Street, London. W.C.2.

TAS/SC 117

QUIZ No. 4

"Next question, Mr. Bigtiffin... How do pukka engineering sahibs set about solving their corrosion problems in the tropics?"



Mr. Bigtiffin squared up to the microphone with the air of a man shouldering the white man's entire burden. "I have been out East 35 years," he said. "I have built in swamps that wanted draining and jungles that had to be cleared, and wherever I've built, I have had to reckon with conditions of heavy rains five months out of twelve. Corrosion has always been one of our biggest bugbears, and it wasn't until a few years ago we discovered a satisfactory method of dealing with it. Metal Coatings. That's what we use nowadays. Sprayed in situ by the British wire process."

"Just how do you spray it?" asked the announcer.

"With a Metallisation Pistol," replied Mr. Bigtiffin emphatically. "That Pistol has meant as much to us as a 15" gun to the Navy."



NO 'GONGS' FOR

Metallisation

Write to Metallisation Limited for booklets and information.

Contracting: Pear Tree Lane, Dudley.

Metal Spraying Plant:

Sales Office: Barclays Bank Chambers, Dudley.

M-W.70.

Manufacturers in HIGH GRADE NON-FERROUS ALLOYS

IN GUNMETAL
PHOSPHOR BRONZE
BRASS, RED METAL
ALUMINIUM, WHITE
BEARING METALS, ETC.
TO ANY ANALYSIS

ESTABLISHED 1872
ON ADMIRALTY, A.I.D. AND WAR OFFICE LISTS

PARK & PATERSON LTD


Metal Merchants, Smelters, and Alloy Manufacturers

PARKHEAD, GLASGOW, E.T.

TELEPHONE:
BRIDGETON 2679

A & C. CODE:
5th EDITION

TELEGRAMS:
"CUPRUM" GLASGOW




The Rototherm principle of temperature measurement allows of a more robust design without sacrificing sensitivity or accuracy. Elements and scale readings to suit almost every industrial and commercial requirement can be supplied.

Rototherm

DIAL THERMOMETERS

THE BRITISH ROTOTHERM CO., LTD., LONDON & PROVINCIAL
Showrooms: 7c, Lower Belgrave St., Victoria, S.W.1. Tel: Sloane 20

and at 87 ST. VINCENT ST., GLASGOW, C.



The fly overcomes **g** (short for gravity) by means of suction pads on its feet which enable it to stay upside down on the ceiling. Can we humans do to overcome **g**? We can go a long way towards it by always beginning with the traditional materials but by thinking in terms of lightness and exploring the great possibilities in the new light alloys that have been developed by H.D.A. Next time you have a production problem . . .


make light work of it with



**HIGH
DUTY
ALLOYS**

HIGH DUTY ALLOYS LIMITED, SLOUGH, BUCKS.
RODS, BILLETS, FORGINGS AND CASTINGS IN 'HIDUMINIUM' ALUMINIUM ALLOYS
(Regd. trade mark)

Lead working machinery



Rolling Mills for widths up to 14 feet. Roll down to 2½ pounds per square yard without doubling or sticking. Large mill needs only four operators to melt, cast, roll, cut and coil. Ward-Leonard drive gives shockless reversal.

Hydraulic Presses for making pipes, glazing bar covers, window lead wire, lead bends, traps, syphons, etc.

Hydraulic Cranes for changing rails and containers in hydraulic presses.


Lead Pipe Coilers for light, medium and heavy section pipes.

Lead Melting Pots for supplying pipes and cable presses. Capacities up to 10 cwt. Suitable for coal, coke or gas.

THE ECLIPSE TOOL CO. LINWOOD NR. GLASGOW
 PHONES: 80, 81 ELDERSLIE. GRAMS: REID, LINWOOD, RENFREWSHIRE



NON-FERROUS CASTINGS




Fully approved by Admiralty and A.I.D.

OUR specialised knowledge is offered to you for castings of **PHOSPHOR BRONZE, GUNMETAL, ALUMINIUM, MANGANESE-BRONZE, and in ALUMINIUM BRONZE** which possesses a Tensile strength of 45 tons per sq. in.

Also:

'BIRSO' Chill Cast Rods, Tubes, Centrifugally Cast Worm-Wheel Blanks, Finishing Propellers and Precision Machined Parts, Ingot Metals,

T.M. BIRKETT & SONS LTD. Hanley, STAFFS
 'PHONE: STOKE-ON-TRENT 2184-5-6. GRAMS: BIRKETT, HANLEY



Production engineers are taking increasing advantage of the ease and speed with which Aluminium and Aluminium Alloys can be spun, pressed or stamped into accurate components • Successful machine forming demands material with close tolerances and consistent properties • British Aluminium sheet, strip and circles provide this consistency and cover the full range of manufacturing requirements. We shall be pleased to advise on their use for any application.

Shape the Future with British Aluminium

THE BRITISH ALUMINIUM CO LTD



SALISBURY HOUSE LONDON EC2

☎ 138-156

HIGH TEMPERATURE MEASUREMENT


★

BAKER LONG LIFE Platinum v. Platinum/Rhodium Thermocouples are made to conform to N.P.L. standards of purity and accuracy.

Both 10% and 13% Rhodium/Platinum v. Platinum Couples in the usual diameters can be supplied from stock. Special sizes can be made quickly to order.


All Couples are thoroughly tested and guaranteed to agree within $\pm 1^{\circ}\text{C}$. with standard calibration curves at any temperature up to 1200°C .

BAKER PLATINUM LIMITED, 52, High Holborn, London, W.C.1.
Chancery 8711.



The "SERVICE" model microscope, designed and built to give a lifetime of efficient work, combining ease of manipulation with precision of movement and absolute rigidity.

CASSEL



CYANIDE BATHS

THE IDEAL METHOD FOR
SURFACE HARDENING
SMALL PARTS



The illustrations show
small typewriter pegs
case hardened in
cyanide.

Precision control of case depth

Uniformly high hardness

Excellent toughness

Clean, bright finish

For details of
'Cassel' Heat-
Treatment Salts
and Salt Bath
Furnaces consult:-

IMPERIAL
NOBEL HOUSE



CHEMICAL INDUSTRIES LTD.
LONDON, S.W.1

CC 131

What's the Answer?



THINK

OF IRON AND STEEL
OF THE DAMP AND ACID LADEN
ATMOSPHERE—OF SALT WATER
ACTION AND OF THE CORROSION
AND WASTAGE CAUSED THEREBY



THINK

OF THEIR EXPOSURE TO SUCH
ATTACK AND OF THEIR
PROTECTION AGAINST IT

IF CORROSION IS YOUR PROBLEM
MELLOZING IS THE ANSWER

(METAL SPRAYING • PROCESS)

MELLOWES & COMPANY LIMITED
SHEFFIELD • LONDON • OLDHAM
ALSO DEPOTS IN ALL PARTS



PRESSURE DIE CASTINGS
WOLVERHAMPTON DIE-CASTING CO., LTD.
GRAISELEY HILL WOLVERHAMPTON
IN ZINC ALLOY—"MAZAK" OF COURSE!




TELEPHONE: 23831-4 LINES

TELEGRAMS: DIE CASTING, WOLVERHAMPTON.

Steel gets its face lifted

— BY FLAME


CONDITIONING



High quality steel, such as is required for Drop Forgings, must be free from the defects which appear in the surface of the ingot, bloom, slab or billet during the process of manufacture. Oxy-Acetylene Hand Deseaming enables individual imperfections of any depth to be removed, either before or after rolling operations, with a greater degree of precision than is possible with pneumatic chipping and in one tenth of the time—giving a faultless finish with an incalculable saving in man hours and machine time. Just one of the many ways in which B.O.C. processes are aiding production in the Steel Industry !

THE BRITISH OXYGEN COMPANY LTD
L O N D O N A N D B R A N C H E S

DAMAXINE PHOSPHOR BRONZES



A range of high-class alloys for bronze bearings to meet general and special requirements, supplied in the form of chillcast solid and cored rods and in ingots and castings.

Produced under the strictest supervision, test and control from selected raw materials. To B.S.I. and all official specifications.

THE MANGANESE BRONZE & BRASS CO. LTD
HANDFORD WORKS, IPSWICH TELEPHONE IPSWICH 2127 TELEGRAMS "BRONZE IPSWICH"

Contents

	PAGE
Institute News and Announcements	xxix
Other News	xxxviii
Local Sections News	xl
Appointments Required and Vacant	xlii
III 14. A Study of Process Variables in the Production of Aluminium Powder by Atomization. By J. S. Thompson	101
III 15. The Surface Tension and Density of Lead-Antimony and Cadmium-Antimony Alloys. By H. T. Greenaway	133
III 16. 1947 Autumn Lecture: The Metallurgical Resources of Scotland. By G. Wesley Austin	149
Metallurgical Abstracts	97

INDEX TO ADVERTISEMENTS

	Page		Page
Allen, Edgar, & Co., Ltd.	vi	Ilford, Ltd.	—
Alumin, Ltd.	—	Imperial Chemical Industries, Ltd.	xxiii
Aluminium Union, Ltd.	ix	Imperial Chemical Industries (Metals) Co., Ltd.	—
Arvimo, Ltd.	xiv	Imperial Smelting Corporation, Ltd.	v
Baird & Tatlock (London), Ltd.	x	International Alloys, Ltd.	—
Baker Platinum, Ltd.	xxii	International Electrolytic Plant Co., Ltd., The.	—
Barnard, H. B., & Sons, Ltd.	—	Johnson, Matthey & Co., Ltd.	—
Bausch & Lomb Optical Co., Ltd.	—	Kodak, Ltd.	iv
Beryllium Smelting Co., Ltd.	—	Lewis, H. K., & Co., Ltd.	xvi
Birkett, T. M., & Sons, Ltd.	xx	Llewellyn Ryland, Ltd.	—
Birlec, Ltd.	xv	McGraw-Hill Publishing Co.	—
Bolton, Thos., & Sons, Ltd.	xii	McKechie Bros., Ltd.	xii
Bloom, James, & Co., Ltd.	xvii	Manganese Bronze & Brass Co., Ltd., The	xxvi
Brown Instrument Co., Ltd.	—	Mellows & Co., Ltd.	xxiv
Bristol's Instrument Co., Ltd.	—	Metallisation, Ltd.	xviii
British Aluminium Co., Ltd., The	xxi	Ministry of Fuel & Power	(Inside back cover)
British Gas Council	—	Mond Nickel Co., Ltd., The	iii
British Insulated Callender's Cables, Ltd.	xxviii	Mullard Wireless Service Co., Ltd., The	—
British Oxygen Co., Ltd., The	xxv	Northern Aluminium, Co., Ltd.	—
British Rototherm Co., Ltd., The	xviii	Park & Paterson, Ltd.	xviii
Bureau of Analysed Samples, Ltd.	xvi	Ridsdale & Co., Ltd.	xvi
Capper Pass & Son, Ltd.	xiv	Sheffield Smelting Co., Ltd., The	—
Cooke Troughton & Simms, Ltd.	—	Siemens-Schukert (Great Britain), Ltd.	—
Copper Development Association	viii	Sozoi (1924), Ltd.	xvi
Croby & Co., Ltd.	(Outside back cover)	Spear & Jackson, Ltd.	—
Charles Bourne & Co., Ltd.	—	Stone, J., & Co., Ltd.	xi
Eclipse Tool Co., The	xx	Sunvic Controls, Ltd.	xvii
Electric Furnace Co., Ltd.	—	Tyseley Metal Works, Ltd.	—
Electric Resistance Furnace Co., Ltd.	(Inside front cover)	Vinten, W., Ltd.	—
Entores, Ltd.	(Outside back cover)	Watson, W., & Sons, Ltd.	xxii
Fisher & Ludlow, Ltd.	—	Wiggin, Henry, & Co., Ltd.	—
Foster Instrument Co., Ltd.	xliii	Wild-Barfield Electric Furnaces, Ltd.	—
Boyle, W. & G., Ltd.	—	Wolverhampton Die-Casting Co., Ltd.	xxiv
Callenkamp, A. & Co., Ltd.	—		
Cibbons Bros., Ltd.	—		
Cleffer, W., & Sons	—		
High Duty Alloys, Ltd.	xix		
Ind, E. (South Bank), Ltd.	vii		
Infroyd, John, & Co., Ltd.	—		
Jughes, F. A., & Co., Ltd.	xiii		

NEWS AND ANNOUNCEMENTS

SYMPOSIUM ON INTERNAL STRESSES IN METALS AND ALLOYS

The symposium, which was referred to in detail in our September issue (pp. xxix-xxxii), was held in London on 15 and 16 October 1947. Thirty-six papers were presented and valuable discussions took place. A notable feature of the meeting was the large attendance that was maintained throughout the sessions, over 300 members and visitors being present.

The conversazione held on the evening of 15 October was very successful, and some interesting exhibits—including a film of Sir Lawrence Bragg's bubble model—were shown.

The papers contributed to the symposium, together with a report of the discussions, will be published as a special volume. The price of the book and approximate date of publication will be announced later, but in the meantime it is requested that all who may desire to purchase this volume will notify the Secretary to that effect, if they have not already done so on the reply form which was sent to them.

The supply of advance copies of the papers is exhausted.

PROFESSIONAL QUALIFICATIONS

Reversing a rule that has been in force for many years, the Council has decided that, in addition to rank, honorific distinctions and university degrees, there may now be printed, in the Institute's publications, such letters denoting membership of *qualifying* bodies as are desired by authors and other contributors. Membership of non-qualifying bodies will not be indicated.

JOINT LIBRARY

Members resident in the United Kingdom are reminded that they may borrow books or periodicals from the Joint Library, on application to the Librarian.

Those who desire them should apply to the Librarian, Joint Library, 4 Grosvenor Gardens, London, S.W.1, to be regularly supplied with the printed copies of the "Additions to the Library".

Certain books and periodicals which are not received in the Library are obtainable for members, on loan, from other sources.

ABSTRACTING AND REVIEWING

The Editor requests that authors of papers published in the more obscure publications, which may not be regularly abstracted in *Metallurgical Abstracts*, shall send to the Institute copies of their papers—where of metallurgical interest—for abstracting, and for subsequent filing in the Joint Library.

Authors of books suitable for notice are also requested to arrange for review copies to be sent to the Editor by their publishers.

AUTUMN MEETING PHOTOGRAPHS

Members may obtain copies of the photographs taken at the Glasgow Autumn Meeting from the photographers, as detailed below:

Group Photograph: Northern Press Photo Agency, Ltd., 29 Waterloo Street, Glasgow, C.2. (Prices, $8\frac{1}{2} \times 6\frac{1}{2}$ in., 10s. 6d. each; 15×12 in., 17s. 6d. each.)

NEWS AND ANNOUNCEMENTS

Dinner and Loch Lomond Photographs: Scottish Studios and Engravers, Ltd., 196 Clyde Street, Glasgow, C.1. (Price 3s. 6d. each.)

REMITTANCES OF MONEY FROM ABROAD

It is requested that when remittances of money are made from abroad, in payment of subscriptions or for publications, a covering note shall be sent *clearly stating the name of the sender* and the purpose for which the money is sent.

Cheques and International Money Orders are frequently received bearing no indication of the name of the sender or of the person or firm to which the goods are to be despatched.

Members whose firms send cheques, &c., on their behalf are also requested to ensure that, in a covering note, it is clearly stated for whom the money is remitted.

MEMBERSHIP ADDITIONS

The undermentioned 12 Ordinary Members and 11 Student Members were elected on 15 October 1947:

Ordinary Members

- CHAUMELLE, Pierre Roger, Manager, Centre of Documentation for the French Iron and Steel Industry, 12 rue de Madrid, Paris 8^e, France.
- CHILTON, Leonard Vincent, M.A., Manager, Intelligence Department, The British Aluminium Company, Ltd., Salisbury House, London Wall, London, E.C.2.
- COLLIER, Thomas William, Production Metallurgist, Thomas Bolton and Sons, Ltd., Froghall, Stoke-on-Trent, Staffordshire.
- FINLAY, Walter Leonard, B.S.Ch.E., M.Eng., Research Metallurgist, Remington Arms Company, Bridgeport, Conn., U.S.A.
- GUY, Professor Albert Glasgow, D.Sc., Associate Professor, Mechanical Engineering Department, North Carolina State College, Raleigh, North Carolina, U.S.A.
- HISCOCK, Walter George, Ph.D., B.Sc., General Manager, National Smelting Company, Ltd., Avonmouth, Bristol.
- MORGAN, Stephen William Kenneth, B.Sc., A.R.S.M., Manager, Research Department, National Smelting Company, Ltd., Avonmouth, Bristol.
- NELSON, Ferguson Ross, B.Sc., Metallurgist, Armstrong Siddeley Motors, Parkside Works, Coventry, Warwickshire.
- RAMA CHAR, T. L., Ph.D., M.Sc., Industrial Chemist and Officer-in-Charge, Bureau of Industrial and Statistical Information, Indian Institute of Science, Bangalore, India.
- VIODE, Jean Alfred Auguste, Powder Metallurgist, 17 rue Collette, Paris 17^e, France.
- WATKINSON, Herbert Henry, Officer-in-Charge, Metallurgical Test House, A.I.S. Test Centre, Middle East.

NEWS AND ANNOUNCEMENTS

WILKINSON, Robert Geoffrey, B.Sc., Deputy Chief Metallurgist, Magnesium Elektron, Ltd., Clifton Junction, Manchester.

Student Members

- ALLARD, Robert William, B.Sc., Student of Metallurgy, King's College, University of Durham, Newcastle-on-Tyne.
- BARTLETT, William Leslie, B.Sc., Student of Metallurgy, University College, Cardiff.
- BELLAMY, Roy Graham, B.Sc., Student of Metallurgy, University College, Cardiff.
- CAULFIELD, Kenneth William, M.Sc., Research Metallurgist, Tin Research Institute, Fraser Road, Greenford, Middlesex.
- GRIEVE, Alan, B.Sc., Student of Metallurgy, University College, Cardiff.
- MACK, Kenneth Alexander, B.Sc., Student of Metallurgy, University College, Cardiff.
- TIPLER, Hedley Roy, B.Met., Assistant Experimental Officer in Metallurgical Research, National Physical Laboratory, Teddington, Middlesex.
- TOMALIN, Peter Frank, B.Sc., Metallurgist, Metropolitan-Vickers Electrical Company, Ltd., Trafford Park, Manchester.
- UPTON, John Charles, B.Sc., Technical Officer (Met.), Imperial Chemical Industries, Ltd., Billingham Division, Billingham, Co. Durham.
- VARLEY, John Henry Oliver, Student of Metallurgy, The University, Birmingham.
- YEOMANS, Donald Eric, Student of Metallurgy, The University, Birmingham.

PERSONALITIES

Dr. C. H. Desch

Dr. Cecil Henry Desch, F.R.S., who has been elected a Fellow of the Institute of Metals, was born in London in 1874, and was educated at Birkbeck School, Kingsland; Finsbury Technical College; University College, London (D.Sc.); and Würzburg University (Ph.D.). In 1902 he joined the Metallurgical Department at King's College, London, and in 1909 was appointed Lecturer in Metallurgical Chemistry at Glasgow University, at which he remained until the end of the 1914-18 war. He was then appointed Professor of Metallurgy at the Royal Technical College, Glasgow, a position which he held until 1920, when, on the death of Professor J. O. Arnold, he succeeded to the Chair of Metallurgy at Sheffield University.

In 1931 Dr. Desch visited the United States, where he was George Fisher Baker Lecturer at Cornell University, and in 1932 was appointed Superintendent of the Department of Metallurgy at the National Physical Laboratory, Teddington, where he remained until his retirement in 1939. More recently Dr. Desch has been closely connected with the iron and steel industry. He was appointed to the Board of Directors of Messrs. Richard Thomas and Company, Ltd., in 1943, to direct the research and development activities of that firm, but, on the amalgamation of the

NEWS AND ANNOUNCEMENTS

Company with Messrs. Baldwins, Ltd., in 1945, he resigned his directorship and has since been associated with the Whitehead Iron and Steel Company, Ltd.

Dr. Desch was President of the Institute of Metals from 1938 to 1940. He was elected a Fellow of the Royal Society in 1923, was President of the Faraday Society from 1926 to 1928, and has been President of the Iron and Steel Institute since 1946. He was awarded the Institute of Metals (Platinum) Medal in 1941; the Bessemer Gold Medal of the Iron and Steel Institute in 1938; and received the honorary LL.D. degree of Glasgow University. He was recently elected a Corresponding Member of the French Academy of Science.



He delivered the Eighteenth May Lecture to the Institute of Metals in 1928 on "The Chemical Properties of Crystals" (*J. Inst.*

Metals, 1928, vol. 39), and is the author of numerous papers on metallurgical and chemical subjects, seven of which are published in the *Journal of the Institute of Metals*. In 1914 and 1919, respectively, he presented the First and Second Reports to the Beilby Prize Committee on "The Solidification of Metals from the Liquid State" (*J. Inst. Metals*, 1914, vol. 11, and 1919, vol. 22). He is also the author of several books, including his "Metallography", "Intermetallic Compounds", "The Chemistry of Solids", and (with F. C. Lea) "Chemistry of Cement and Concrete".

Lieut.-Colonel Sir John Greenly

Lieut.-Colonel Sir John Henry Maitland Greenly, K.C.M.G., C.B.E., M.A., who has been elected a Fellow of the Institute of Metals, was born on 25 July 1885, and is the second son of the late E. H. Greenly, J.P., D.L., of Titley Court, Herefordshire, and Sarah, daughter of the late Lieut.-General Bowes Foster.

Educated at Charterhouse and Trinity College, Oxford, where he graduated, he was trained as a Civil Engineer. Commissioned in 1906 in the Herefordshire Regiment (T.F.), he was promoted Captain in 1912, and served in the 1914-18 war, being appointed to be a Staff Captain and Brigade Major in 1916, promoted to Lieut.-Colonel in 1917, and twice mentioned in despatches. He was Assistant Controller of Inspection of Munitions of War at the Ministry of Munitions from 1916 to 1919. In 1919 he was made a C.B.E.

In 1920 he was appointed Joint Managing Director of Messrs. William Foster, Pascoe, Grenfell and Company, copper manu-

NEWS AND ANNOUNCEMENTS

facturers and smelters of London and Swansea, and subsequently Joint Managing Director of Messrs. British Copper Manufacturers,



Ltd. He joined the Board of Messrs. Babcock and Wilcox, Ltd., in 1929, and became Chairman of the Executive Committee and Deputy Chairman of the Company in 1932, and Chairman in 1937. He is also a Director of other Companies.

Since 1937 Sir John has been Chairman of the British Non-Ferrous Metals Research Association, in which position he has given outstanding service to the industry. He has also held numerous other positions of eminence in the fields of science and industry. He was Chairman of the Coal-Burning Appliances Joint Consultative Board in 1936; a member of the Advisory Council to the Committee of the Privy Council for Scientific and Industrial Re-

search from 1937 to 1943; a member of the Industrial Advisory Panel to the Air Ministry from 1938 to 1939; Chairman of the Prime Minister's Advisory Panel of Industrialists on Rearmament from 1938 to 1939; Contoller-General of the British Supply Board in Canada and the United States, 1939-1940; Deputy Chairman and Administrator, Fire Prevention Executive, 1941-1945; a member of the Fire Prevention (Operational) Committee (Ministry of Home Security), 1941-1945; member of the Fuel Research Board, 1942-1947; member of the Advisory Panel to the Minister of Reconstruction, 1942; Chairman of the Bricks Appeal Tribunal (Ministry of Works), 1942-1945; member of the Fuel and Power Advisory Council (Ministry of Fuel and Power), 1944-1946; Member of Council of the British Coal Utilization Research Association, 1938-1946; Vice-President of the Coal Utilization Joint Council, 1945-1946; and is a Member of Council of the British Welding Research Association; a Member of the Institution of Mechanical Engineers, the Institute of Fuel, and the Institution of Engineering Inspection, and a Fellow of the Institution of Metallurgists.

In 1941, he was created a Knight Commander of the Most Distinguished Order of St. Michael and St. George.

Sir John was President of the Institute of Metals from 1942 to 1944, and is also a Past-President of the Institute of Fuel, the Institution of Engineering Inspection, and the Combustion Appliance Makers' Association (Solid Fuel).

In 1946 he was awarded the Institute of Metals (Platinum) Medal in recognition of his outstanding services to the industry. As a Past-President he remains a Member of the Council, which thus continues to benefit from his advice and inspiration.

PERSONAL NOTES

MR. J. L. ASTON has left Cambridge and is now at Sheffield University, to undertake research on the rapid heat-treatment of steel, particularly from the point of view of the metallurgy of the induction hardening of steel.

MR. K. W. J. BOWEN, B.Sc., is now at the Goldsmiths' Laboratory, Cambridge University. His address is Sidney Sussex College.

PROFESSOR SIR LAWRENCE BRAGG, O.B.E., Sc.D., F.R.S., has retired from the Advisory Council for Scientific and Industrial Research.

MR. R. V. BRYAN, L.I.M., has left the Ministry of Supply to take up an appointment as Personal Assistant to the Steel Dept. Manager, Sanderson Brothers and Newbould, Ltd., Sheffield.

MR. STANLEY W. CADDEN has been appointed Managing Director of the Tomey Group of Companies, comprising Joseph Tomey and Sons, Ltd., Aston, Birmingham; Excelsior Gauge Company, Ltd., Erdington, Birmingham; L. Tomey, Ltd., Erdington, Birmingham; and J. L. Tomey (Coventry), Ltd., Bromsgrove.

MR. R. W. CAHN has concluded his work at the Cavendish Laboratory, Cambridge, and has taken up an appointment with the Atomic Energy Research Establishment, Ministry of Supply, Harwell. His temporary address is Winnoway Farm, Harwell, near Didcot, Berks.

MAJOR H. B. DESHPANDE, J.P., M.Sc., F.I.M., Chief Chemist and Metallurgist, East Indian Railway, who is in England on a long leave, made an extensive tour of Canada and the United States in August last and has now returned to London. His address is c/o Thomas Cook and Son, Ltd., 45 Berkeley Street, London, W.1.

MR. V. J. DONNELLY, A.I.M., has returned home to South Africa. His address is c/o National Bolts and Rivets, Ltd., 49 Rawbone Street, Ophirton, Johannesburg.

DR. D. S. EPELSHEIMER, D.S., has left the Metal Hydrides Corporation, Beverly, Mass., U.S.A., on appointment as Associate Professor of Metallurgical Engineering at the Missouri School of Mines and Metallurgy, Rolla, Miss.

MR. K. S. FOSTER has sold his holding in Cookson Hermitage, Ltd., and, after a long illness, has now joined Associated Combustion, Ltd., Meonstoke, Southampton.

MR. F. F. GORDON, Assoc.Met., has been appointed Managing Director of Spear and Jackson, Ltd., Sheffield.

MR. A. T. GREEN, O.B.E., F.R.I.C., F.Inst.P., Director of Research of the British Refractories Research Association and of the British Ceramic Society, has been appointed Honorary General Secretary to the British Ceramic Society, in succession to the late Dr. J. W. Mellor.

SIR WILLIAM T. GRIFFITHS, D.Sc., F.R.I.C., F.I.M., Chairman and Managing Director of The Mond Nickel Company, Ltd., and a Past-President of the Institute, has been appointed by the Lord President of the Council to be a member of the Advisory Council for Scientific and Industrial Research.

NEWS AND ANNOUNCEMENTS

MR. C. F. HARRIS, B.Sc., A.R.S.M., has completed his course at the Royal School of Mines and has been called up to serve in H.M. Forces. Correspondence should be addressed to The Homestead, 46 Murray Road, Northwood, Middlesex.

MR. W. M. HOGENDOORN has, since 1 July 1947, been in charge of the metallurgical laboratory, concerned with internal combustion engine development, of the N.V. Metaalindustrie "Johan de Witt" at Dordrecht, Holland. This Company is a branch of the N. V. Philips Gloeilampenfabrieken.

MR. L. C. HOLLYHEAD graduated in June with an Honours degree (B.Sc.) from the School of Industrial Metallurgy, Birmingham University.

MR. E. HUNTER has been appointed Manager of the Foundry Equipment Department of the Incandescent Heat Co., Ltd.

DR. L. JENÍČEK has been appointed Research Director of the United Steelworks National Corporation, Czechoslovakia, but retains his connection with the Czechoslovak Mining and Metallurgical Institute at Ostrava.

MR. KENNETH S. JEPSON has been awarded the degree of B.Met. (Non-Ferrous) of the University of Sheffield.

MR. H. O. LUDKEY has acquired British nationality, and has changed the spelling of his name, from Luedke.

SIR ANDREW McCANCE, D.Sc., A.R.S.M., F.R.S., has retired from the Advisory Council for Scientific and Industrial Research.

MR. I. MANNING, has left David Brown and Sons, Ltd., Lockwood, Huddersfield, and is now Assistant Technical Officer with Imperial Chemical Industries, Ltd., Billingham Division, Billingham, Co. Durham. His private address is 19 Oxford Road, Thornaby-on-Tees.

MR. A. J. W. MOORE, B.Sc., has left Cambridge, to return to the C.S.I.R. Section of Tribophysics, Melbourne University. His private address is 27 Summerhill Avenue, East Malvern, Melbourne, S.E.5, Vic., Australia.

MR. JAMES NAYSMITH now holds an appointment with the Anglo-Iranian Oil Company, Ltd. His address is: Reg. No. 6596, SQ 133/5 Braun, c/o Anglo-Iranian Oil Company, Ltd., Abadan, South Iran.

MR. M. C. NICKSON, B.Sc., A.I.M., has changed his place of employment with The Mond Nickel Company, Ltd., to Birmingham.

MR. F. S. PASCHEK, B.Sc., A.R.S.M., has left the Royal School of Mines, London.

SIR CLIFFORD PATERSON, O.B.E., F.R.S., has been appointed Chairman of the General Council of the British Standards Institution.

MR. B. W. PRINCE has left the David Brown Foundries Company, Penistone, to take up an appointment with Firth-Vickers Stainless Steels, Ltd., Sheffield.

MR. COLIN W. ROBERTS, B.Sc., A.I.M., has left the A.I.D. Test House, Harefield, and is now at the Research Department of the National Smelting Company, Ltd., Avonmouth.

NEWS AND ANNOUNCEMENTS

MR. J. A. ROBERTS, who graduated with honours in metallurgy from the University College of Swansea, is now engaged at the Wern Aluminium Works of the Light Alloy Section of Richard Thomas and Baldwins, Ltd. His new address is Lodway, 5 Upper Cimla, Neath, South Wales.

MR. JAMES B. RUSSELL, B.S., has resigned his post as Metallurgist at the Naval Research Laboratory at Washington, in order to take up a full-time graduate study of physical metallurgy at the University of California. His present address is Hotel Carlton, Room 508, 2338 Telegraph Avenue, Berkeley 4, Cal., U.S.A.

MR. E. C. SMITH has been awarded the degree of Doctor of Science of the Case Institute of Technology, Cleveland, O., U.S.A.

MAJOR P. L. TEED, A.R.S.M., on 9 October 1947, at the École Nationale Supérieure de l'Aéronautique, delivered a lecture to the Association Française des Ingénieurs et Techniciens de l'Aéronautique, on "Les Propriétés des Matériaux Métalliques aux Altitudes Stratosphériques".

MR. J. G. M. TURNBULL, B.Sc., Chief Chemist to C. A. Parsons and Company, Ltd., Newcastle-upon-Tyne, was elected a Fellow of the Institution of Metallurgists in January 1947.

MR. T. HENRY TURNER, M.Sc., has been elected a Member of the Institution of Mechanical Engineers.

BIRTH

LEES. On 22 September 1947, at Westminster Hospital, London, S.W.1, to May (née Robertson), wife of D. C. G. Lees, M.A., a daughter.

DEATHS

The Editor regrets to announce the deaths of:

MR. G. C. PITCAIRN, of Metallisation, Ltd., Dudley, on 17th October 1947.

MR. J. S. GLEN PRIMROSE, A.R.T.C., Chief Metallurgist, The Rover Company, Ltd., Coventry, and an Original Member of the Institute, on 2 October 1947.

MR. H. B. PULSIFER, Ch.E., M.S., Metallurgist, the Ferry Cap and Set Screw Company, Cleveland, O., U.S.A., on 1 September 1946.

Note: Will members (in addition to informing the Institute's administrative department of changes of address, occupation, &c.) kindly notify the Editor, separately, of all changes of occupation, appointments, awards of honours and degrees, &c., as these are matters which interest their fellow members? Such notes should reach the Editor not later than the 21st day of each month for publication in the next month's issue.

OTHER NEWS

GENERAL DISCUSSION ON THE PHYSICAL CHEMISTRY OF
PROCESS METALLURGY

The Faraday Society plans to hold, in the latter half of September 1948, a general discussion on the physical chemistry of process metallurgy. It is intended that the discussion shall be devoted to the thermodynamics and kinetics of the high-temperature reactions involved in smelting and refining, and it is proposed to exclude reactions occurring in mechanical working and heat-treatment and also electrochemical processes in aqueous solutions. Thermodynamics will include thermochemical, free energy, and equilibrium studies, and kinetics will include both chemical reactions and diffusion processes.

Prospective contributors are requested to forward to the Secretary, The Faraday Society, 6 Gray's Inn Square, London, W.C.1, summaries of any papers that they would like to submit, indicating the subject matter and the method of treatment, as early as possible and not later than 1 February 1948. Papers accepted will be required to be submitted by 1 July 1948.

DEUTSCHE GESELLSCHAFT FÜR METALLKUNDE

It is learned that, under the direction of Professor Dr. Glocker, Technische Hochschule, Stuttgart, American Zone, the Deutsche Gesellschaft für Metallkunde has been revived.

AMERICAN FOUNDRYMEN'S ASSOCIATION RESEARCH
PROJECTS

Three specific interest divisions of the American Foundrymen's Association have launched research projects on fundamental problems in foundry technology. Investigations proposed by the research groups of the aluminium and magnesium, brass and bronze, and malleable divisions, have been approved.

The light metals group will continue and expand the study of centrifugal casting of aluminium and magnesium alloys it has conducted during the past year. Plans for the immediate future include the design of experimental castings and the compilation of data on such aspects as operational requirements, density, grain-size, mechanical properties, production yield, and segregation. Mr. R. F. Thomson, Metallurgist with the International Nickel Co., Detroit, is Chairman of the Division Research Committee.

A comprehensive investigation of tin bronze test-bars is to be undertaken by the brass and bronze research body, headed by Dr. Blake M. Loring, Chief of the Non-Ferrous Division of the Naval Research Laboratory, Washington, D.C. Accurate determination of metal quality through the fracture test will be sought. As-cast structure of the bars will be examined by metallographic, radiographic, fractographic, and other means found desirable. It is anticipated that, through determination of the proper test-bar design, melting conditions, and means of breaking the specimens, the fracture test may be established as a reliable, rapid, and inexpensive method of analysing the quality of melts before castings are poured.

NEWS AND ANNOUNCEMENTS

The malleable division project is intended to yield data on the most desirable microstructure for pearlitic malleable-iron castings to be selectively hardened by flame or induction heating.

BRITISH COUNCIL SCHOLARSHIPS

The British Council has awarded scholarships for 1947-48 to 256 graduates or others of like status from 62 countries, including the Dominions and Colonies, to enable them to undertake a year's specialist study in the United Kingdom. In addition, 106 British Council scholars have had their scholarships extended for a further year. The subjects of study cover a wide range, and the majority of scholars are studying in British Universities or University Colleges.

FOURTH PLENARY WORLD POWER CONFERENCE

The conference will be held in London in 1950. This decision was taken by the International Executive Council of the World Power Conference at its recent meeting at The Hague.

ACTA CRYSTALLOGRAPHICA

A new journal of crystallography, *Acta Crystallographica*, sponsored by the recently-formed International Union of Crystallography (see August issue of the *Journal*, p. xli) will start publication in 1948. It is intended to take the place of *Zeitschrift für Kristallographie*, but, in recognition of the rapid development of structural studies in recent years, it is intended to be somewhat broader in its scope and to concern itself with all those physical and chemical properties of matter intimately connected with atomic arrangement.

The journal will be under the editorship of P. P. Ewald, a former editor of the *Zeitschrift für Kristallographie*, and a panel of regional co-editors. It will appear in six issues per year. The annual subscription will be \$10 or £2 10s. European subscribers should write to the Cambridge University Press, Euston Road, London, N.W.1. Arrangements have been made for those in the U.S.A. and Canada to obtain the journal through the American Institute of Physics, 57 East 55th St., New York 22, N.Y.

Articles for publication will be accepted in English, French, German, or Russian, and authors are now invited to submit manuscripts for consideration by the co-editors: in English, to R. C. Evans, Crystallographic Laboratory, Cavendish Laboratory, Cambridge, or to I. Fankuchen, Polytechnic Institute of Brooklyn, Brooklyn 2, N.Y., U.S.A.

QUARTERLY JOURNAL OF MECHANICS AND APPLIED MATHEMATICS

Published quarterly by the Oxford University Press, under the editorship of Dr. V. C. A. Ferraro and Dr. G. C. McVittie, the first issue of this new journal will be published in April 1948. The journal will cover the fields of hydrodynamics including aerodynamics, sound and dynamical meteorology; elasticity and plasticity; numerical methods, including calculating machines and relaxation methods; non-linear dynamics; ballistics; classical electromagnetism including the propagation of electric waves in

NEWS AND ANNOUNCEMENTS

space and in wave-guides. Contributions on these subjects are likely to contain references to published experimental work; and when new experimental work is undertaken in this connection, it might be suitable for publication in the journal.

Papers to be considered for the early issues should be sent before December 1947, addressed by name to one or other of the executive editors, at King's College, Strand, London, W.C.2.

MEMORIAL TO DENIS PAPIN

The little commune of Chitenay (Loire-et-Cher, France) celebrated the centenary of the birth of Denis Papin on 20 July at the Closerie des Communes.

A commemorative plaque was unveiled by MM. Albert Caquot and Albert Portevin, members of the Institut de France, representatives of the Académie des Sciences. During the banquet which followed the ceremony, very appreciative speeches were made by Professor E. N. da C. Andrade, a Fellow of the Royal Society, of which Denis Papin was a corresponding member, by Mr. Dickinson, President of the Newcomen Society, by Mr. Cortesao, representative of UNESCO and by Professor Cabannes, Vice-Chancellor of the University of Paris.

LOCAL SECTIONS NEWS

At a special meeting of the London Local Section, to be held at 4 Grosvenor Gardens, London, S.W.1, on Thursday, 27 November 1947, at 7 p.m., Dr. W. J. Kroll will give a lecture on "Malleable Titanium and Zirconium—Two Metals of the Future Made on a Commercial Scale".

The title of the Swansea Local Section has been changed to South Wales Local Section.

DIARY FOR DECEMBER

LOCAL SECTIONS MEETINGS

Birmingham Local Section.—Students' Night. (James Watt Memorial Institute, Great Charles Street, Birmingham, Thursday, 4 December 1947, at 6.30 p.m.)

London Local Section.—Dance. (4 Grosvenor Gardens, London, S.W.1, Friday, 5 December 1947. Tickets (single), price 16s., obtainable from Dr. E. C. Rhodes, c/o The Mond Nickel Co., Ltd., Development and Research Department, Bashley Road, London, N.W.10.)

Scottish Local Section.—Mr. R. E. Wilson: "Electroplating Practice and Engineering Application." (Institution of Engineers and Shipbuilders in Scotland, 39 Elmbank Crescent, Glasgow, C.2, Monday, 8 December 1947, at 6.30 p.m.)

Sheffield Local Section.—Mr. H. Evans, Assoc.Met.: "Surface Finish and Electrolytic Polishing." (Mining Lecture Theatre, Department of Applied Science, The University, St. George's Square, Sheffield, Friday, 19 December 1947, at 7.30 p.m.)

NEWS AND ANNOUNCEMENTS

South Wales Local Section.—Dr. R. Higgins, B.Sc., and Mr. D. W. Hopkins, B.Sc.: Accounts of visits to Canada and the United States under the auspices of the Nuffield Foundation Scheme. (Y.M.C.A., Swansea, Tuesday, 2 December 1947, at 6.30 p.m.)

OTHER MEETINGS

British Society for International Bibliography.—Dr. Marjorie Plant: "A Project for a Periodicals Indexing Service"; and Henry Rottenburg: "The Fundamentals of Classifying, Indexing, and Filing References." (Institution of Electrical Engineers, Savoy Place, London, W.C.2, Wednesday, 17 December 1947, at 2.30 p.m.)

Cleveland Institution of Engineers.—W. Udall: "Combination Rolling Mills." (Cleveland Scientific and Technical Institution, Corporation Road, Middlesbrough, Monday, 1 December 1947, at 6.30 p.m.)

Geological Society of London.—Ordinary evening meeting. (Burlington House, Piccadilly, London, W.1, Wednesday, 10 December 1947, at 5 p.m.)

Institute of Physics, Industrial Radiology Group.—R. Halmshaw: "The Radiographic Examination of Welded Repairs in Casting." (London, Friday, 5 December 1947, at 6.30 p.m.)

Institute of Physics, Midland Branch.—Dr. C. Sykes, F.R.S.: "Physics and Steel Making." (Birmingham, Thursday, 18 December 1947, at 6 p.m.)

Institute of Welding, South London Branch.—J. A. Dorratt: "Welding in Marine Engineering." (Institute of Marine Engineers, 85-88 The Minories, London, E.C.3, Thursday, 11 December 1947, at 6.30 p.m.)

Institute of Welding, West of Scotland Branch.—W. H. Millwood: "The Practical Application of Flash Butt Welding to Modern Production." (Institution of Engineers and Shipbuilders in Scotland, 39 Elmbank Crescent, Glasgow, C.2, Wednesday, 17 December 1947, at 6.45 p.m.)

Institution of Civil Engineers.—Professor Sir Charles Inglis, O.B.E., M.A., LL.D., F.R.S.: "Mathematics in Relation to Engineering, with Special Reference to a Paper by the Lecturer on Shear-Stress Determination." (The Institution, Great George St., London, S.W.1, Tuesday, 16 December 1947, at 5.30 p.m.)

Institution of Electrical Engineers, North-Western Installations Group.—M. E. Haine, B.Sc.: "The Design and Construction of a New Electron Microscope." (Engineers' Club, Albert Square, Manchester, Tuesday, 16 December 1947, at 6 p.m.)

Institution of Mechanical Engineers, Applied Mechanics Group.—W. A. P. Fisher, M.A.: "Basic Physical Properties Relied on in the Frozen Stress Technique"; and R. B. Heywood, B.Sc.: "Modern Applications of Photoelasticity." (The Institution, Storey's Gate, London, S.W.1, Friday, 12 December 1947, at 5.30 p.m.)

NEWS AND ANNOUNCEMENTS

Institution of Mining and Metallurgy.—General Meeting. (Geological Society, Burlington House, Piccadilly, London, W.1, Thursday, 18 December 1947, at 5 p.m.)

Institution of Structural Engineers, Lancashire and Cheshire Branch, Graduates' and Students' Section.—J. Martin: "Welded Structures." (Milton Hall, Deansgate, Manchester, Tuesday, 2 December 1947, at 7 p.m.)

Institution of Structural Engineers.—Professor R. V. Southwell, LL.D., F.R.S.: "Relaxation Methods as Applied to Structures." (The Institution, 11 Upper Belgrave Street, London, S.W.1, Thursday, 18 December 1947, at 5.55 p.m.)

Leeds Metallurgical Society.—H. G. Warrington: "Aluminium Alloys." (Main Lecture Theatre, Chemistry Department, The University, Leeds, Wednesday, 3 December 1947, at 7 p.m.)

Leeds Metallurgical Society.—Buffet Dance. (Astoria Ballroom, Leeds, Thursday, 4 December 1947, at 8 p.m. to 2 a.m.)

Manchester Metallurgical Society.—Ivor Jenkins, M.Sc.: "Controlled Atmospheres for Heat-Treatment of Metals." (Engineers' Club, Albert Square, Manchester, Wednesday, 10 December 1947, at 6.30 p.m.)

Newport and District Metallurgical Society.—A. H. Waine: "Forged Steel Rolls." (Technical College, Newport, Saturday, 13 December 1947, at 6.30 p.m.)

Sheffield Metallurgical Association.—Discussion on "Ingot Surface Defects", to be opened by T. Arnold, N. H. Bacon, and G. E. Howarth. (198 West St., Sheffield, Tuesday, 16 December 1947, at 7 p.m.)

Sheffield Society of Engineers and Metallurgists.—Symposium on "The Use of Liquid Fuel in Open-Hearth Furnaces". (Royal Victoria Station Hotel, Sheffield, Monday, 15 December 1947, at 6.15 p.m.)

Swansea and District Metallurgical Society.—Discussion on "Oil-Firing of Metallurgical Furnaces". Introduced by R. W. Evans, M.Met., A. M. Gabe, B.Sc., and J. S. Lewis. (Royal Institution of South Wales, Swansea, Saturday, 13 December 1947, at 6.30 p.m.)

West of Scotland Iron and Steel Institute.—G. S. T. Martin: "Maintenance of Steel Works Plant." (Institution of Engineers and Shipbuilders in Scotland, 39 Elmbank Crescent, Glasgow, C.2, Friday, 19 December 1947, at 6.45 p.m.)

APPOINTMENT REQUIRED.

METALLURGICAL CHEMIST (35), now managing general non-ferrous foundry, seeks executive post suited to his knowledge and ability. Extensive experience aluminium alloy manufacture and working; with Company of repute. Special knowledge high-tensile castings. Sound technical training, B.Sc., Member Institute of Metals and Institute of British Foundrymen. Can control labour efficiently and get results. Reply Box No. 217, Institute of Metals, 4 Grosvenor Gardens, London, S.W.1.

NEWS AND ANNOUNCEMENTS

APPOINTMENTS VACANT.

To conform to the requirements of the Control of Engagements Order, 1947, these advertisements are published for the information of those only who are "excepted persons" under the Order.

ANALYTICAL CHEMISTS required who should preferably be qualified and have experience in the assaying of non-ferrous metals, minerals, and by-products, including the rarer metals. Liberal salary will be paid. Apply to Derby and Co., Ltd., Cheyne House, 62-63 Cheapside London, E.C.2.

THE BRITISH IRON AND STEEL RESEARCH ASSOCIATION.

PHYSICIST or METALLURGIST with X-ray crystallographic experience required by the above Association for research on the surfaces of metals and coatings. University degree in physics or metallurgy essential. Appointment is in the Scientific Officer grade, age range 22-30. Salary £350-£550 according to age, qualifications, and experience. Location of work Swansea. Written applications only giving full curriculum vitae to the Personnel Officer, B.I.S.R.A., 11 Park Lane, London, W.1.

METALLURGIST required by the above Association for research on the surfaces of metals and coatings. University degree essential, higher degree desirable. Appointment is in the Scientific Officer grade, age range 25-30. Salary £400-£550 according to age, qualifications, and experience. Location of work Swansea. Written applications only giving full curriculum vitae to the Personnel Officer, B.I.S.R.A., 11 Park Lane, London, W.1.

MECHANICAL AND ELECTRICAL ENGINEER with University degree, aged about 35, preferably but not essentially with some experience in the rolling section of the iron and steel industry, required by medium-sized public limited company in North-West. Commencing salary £1250 per annum. Reply giving particulars of education, experience, position held, and age to Box No. 216, Institute of Metals, 4 Grosvenor Gardens, London, S.W.1.

The **CIVIL SERVICE COMMISSIONERS** invite applications for two posts in the Ministry of Supply, both of which are graded as either **PRINCIPAL SCIENTIFIC OFFICER** or **SENIOR SCIENTIFIC OFFICER**. Candidates must be British subjects born on or before 1 August 1915, and must possess a First or Second Class Honours degree in metallurgy.

For Post I, at Headquarters in London, candidates should have experience in the field of research and development on alloys and high temperature materials. The successful candidate will be responsible for handling research work connected with high-temperature alloys and materials for use in gas turbines and other engines.

For Post II, at the Royal Aircraft Establishment, Farnborough, Hants., candidates should have experience in the metallography of light alloys. The successful candidate will be required to undertake research and development work on light alloys used in aircraft production.

Both appointments are permanent with superannuation benefits under the Federated Superannuation System for Universities.

Successful candidates will be appointed as Principal Scientific Officer or Senior Scientific Officer according to their qualifications and experience, on one of the following inclusive salary scales:—

Principal Scientific Officer.

Post I.—£900-£1220.

Post II.—£860-£1155.

Senior Scientific Officer.

Post I.—£650-£850.

Post II.—£620-£810.

Rates for women are somewhat lower.

Forms of application are obtainable from the Secretary, Civil Service Commission, Scientific Branch, 27 Grosvenor Square, London, W.1, quoting No. 2032, to whom completed application forms should be returned not later than 9 December 1947.

OSTER

*Specialists in the manufacture
of Pyrometers for over 30 years.*

TER INSTRUMENT CO., LTD., LETCHWORTH, HERTS

'Phone: Letchworth 984 (3 lines). Grams: "Resilia," Letchworth.

"NON-METALLIC INCLUSIONS IN STEEL"

. . . by M. Baeyerztz

This book brings together, for the first time under a single cover, enough the basic principles which govern the formation of inclusions, the estimation of their amount in commercial products, and the identification of their mineralogical character to afford the beginner an introduction to the subject. It presents signposts that keep the beginner from tripping in the crevasse that sometimes seems to lie between the fields of metallurgy, mineralogy, and physical chemistry.

"Inclusions" gives you a survey of the nature and origin of the common types of non-metallic inclusions, and methods that may be used to study them. The kinds of non-metallic inclusions are generally recognized, and these are considered carefully. One type are those which are entrapped in the steel inadvertently; the other, those which separate from it because of a change in temperature composition. The book contains many illustrations and charts.

135 Pages. Red Cloth Binding. 71 Illustrations. 9 x 6 in. \$3.

AMERICAN SOCIETY FOR METALS
7301 EUCLID AVENUE CLEVELAND 3, OHIO

RECENTLY PUBLISHED AN INTRODUCTION TO THE ELECTRON THEORY OF METALS

by G. V. RAYNOR, M.A., D.Phil.

Research Fellow in Theoretical Metallurgy, Birmingham University

Bound in cloth. 98 pages, with 62 figs.

7s. 6d. post free. (3s. 9d. post free to members)

Specially commissioned by the Institute of Metals, this book has been written for the older metallurgist whose knowledge of pure physics is insufficient to enable him to come readily to terms with the modern theoretical work on the metallic state. ● The author deals with the new approach to metallurgy, some basic principles of atomic theory, the Bohr theory of the atom, the probability conceptions, application to metals, the effect of crystal structure, application to alloy structures, approximations involved in the results of the electron theories, insulators and conductors, magnetic properties of metals and alloys, and the cohesion of metals.

This is a book which should be read by every metallurgist.

INSTITUTE OF METALS
4 GROSVENOR GARDENS, LONDON, S.W.1.

*Revised Prices of Institute Publications (Post Free)
from 22nd May 1947*

INSTITUTE OF METALS PUBLICATION.	Pub- lished Price.	Members Rate (one copy of each).	Book- sellers and Library. Rate.
	£ s. d.	£ s. d.	£ s. d.
JOURNAL, bound in cloth, per vol. (annual)	3 0 0	1 10 0	2 10 0
METALLURGICAL ABSTRACTS, bound in cloth, per vol. (annual)	3 0 0	1 10 0	2 10 0
JOURNAL AND METALLURGICAL AB- STRACTS, bound in cloth, per annum	5 0 0	3 0 0	4 3 4
(MONTHLY) JOURNAL AND METALLUR- GICAL ABSTRACTS, with annual index and proceedings issues and binding cases, per annum	5 0 0	3 0 0	4 3 4
(MONTHLY) JOURNAL AND METALLUR- GICAL ABSTRACTS, per issue	7 6	3 9	6 3
GENERAL INDEXES, bound in cloth, per vol.	1 0 0	10 0	16 8
PERS (back issues), per copy	2 6	1 3	2 1
<i>Special Publications.</i>			
BIBLIOGRAPHIES:			
No. 1.—“The Structure of Metals and Alloys”, by W. Hume-Rothery. Fifth reprint (revised) (1947; reprinting)	4 6	2 3	3 9
No. 2.—“Constitution of Alloys Bibliography”, by J. L. Haughton (1942)	3 6	1 9	2 11
Supplement No. 1 to ditto (1944)	9	5	7
No. 3.—“Atomic Theory for Students of Metal- lurgy”, by W. Hume-Rothery. First reprint (revised) (1947)	7 6	3 9	6 3
No. 4.—“An Introduction to the Electron Theory of Metals”, by G. V. Raynor (1947)	7 6	3 9	6 3
ANNOTATED EQUILIBRIUM DIAGRAMS, per copy	2 0	1 0	1 8
No. 1 (Al-Zn); No. 2 (Cu-Sn); No. 3 (Cu- Zn); No. 4 (Cu-Al); No. 5 (Al-Mg); No. 6 (Pb-Sn).			

DISCOUNT FOR SERIES

a discount of 10% will be allowed on all orders of runs of 10 volumes or more,
a special discount of 25% is allowed on orders for complete sets of either the
Journal or Metallurgical Abstracts.

NOTICE TO AUTHORS OF PAPERS

1. **Papers will be considered for publication from non-members as well as from members of the Institute.** They are accepted for publication in the *Journal*, and not necessarily for presentation at any meeting of the Institute, and should be addressed to The Editor of Publications, The Institute of Metals, 4 Grosvenor Gardens, London, S.W.1.
2. **Papers suitable for publication may be classified as :**
 - (a) Papers recording the results of original research;
 - (b) First-class reviews of, or accounts of, progress in a particular field;
 - (c) Papers descriptive of works methods, or recent developments in metallurgical plant and practice.
3. **Manuscripts and illustrations** must be submitted in duplicate. MSS. must be typewritten (*double-line spacing*) on one side of the paper only, and authors are required to sign a declaration that neither the paper nor a substantial part thereof has been published elsewhere. MSS. not accepted will be returned within 6 months of receipt.
4. **Synopsis.** Every paper must have a synopsis (not exceeding 250 words in length), which, in the case of results of research, should state its objects, the ground covered, and the nature of the results. The synopsis will appear at the beginning of the paper.
5. **References** must be collected at the end of the paper, and must be numbered. Initials of authors must be given, and the Institute's official abbreviations for periodical titles (as used in *Met. Abs.*) must be used where known. References must be set out in the style :
 1. W. Hofmann and W. Jäniche, *Z. Metallkunde*, 1936, **28**, 1 (i.e. year, volume, page).
6. **Illustrations.** Each illustration must have a number and description; only one set of numbers must be used in one paper. The set of *line figures* sent for reproduction must be drawn in Indian ink on smooth white Bristol board, tracing cloth, or good-quality drawing paper. Co-ordinate paper is not desirable, but if used must be blue-lined with the co-ordinates to be reproduced *finely* drawn in Indian ink. All lettering and numerals, &c., should be in *pencil*. Figures should be drawn approximately twice the size intended for reproduction. *Photographs* must be restricted in number, owing to the expense of reproduction, and must be trimmed to the smallest possible of the following sizes, consistent with adequate representation of the subject : 3 in. deep by 4 in. wide (two photomicrographs to a plate); 3 in. deep by 2½ in. wide (four to a plate); 2 in. deep by 2½ in. wide (six to a plate). Magnifications of photomicrographs must be given in each case. Photographs for reproduction should be loose, not pasted down (and not fastened together with a clip, which damages them), and the figure number should be written on the back of each. Lengthy descriptions to photomicrographs should be avoided where possible, owing to the very limited space available on the plates. Owing to limitations of paper supplies, illustrations that are not *essential* to the appreciation of the paper should not be included. Only in exceptional cases will illustrations be reproduced if already printed and readily available elsewhere.
7. **Tables or Diagrams.** Results of experiments, &c., may be given in the form of tables or figures, *but* (unless there are exceptional reasons) *not both*.
8. **Overseas Authors.** Authors resident in countries distant from Great Britain are requested to name, if possible, agents in Britain to whom may be referred matters concerning their papers, including proofs for correction. Translations from foreign languages should preferably be accompanied by a copy of the MS. in the language of the author.
9. **Reprints.** Individual authors are presented with 50, two authors with 70, and three with 90, reprints (in cover) from the *Journal*. Limited numbers of additional reprints can be supplied at the author's expense if ordered before proofs are passed for press. (Orders should preferably be placed when submitting MSS.)

A STUDY OF PROCESS VARIABLES IN THE PRODUCTION OF ALUMINIUM POWDER BY ATOMIZATION.*

By J. S. THOMPSON,† B.Sc., STUDENT MEMBER.

SYNOPSIS.

The process of molten-metal atomization has long occupied a position of major importance among the methods of production of metal powders, and its application to aluminium has been common, in various modifications, for many years. Presumably because of the numerous ways in which this process may be performed, there has been little information published about the subject, and therefore a study has been made of the effects of certain variables upon the most important characteristics of the product and the method of operation. Particular attention has been paid to the rate at which atomization proceeds, the size grading of the powder, and the ease and efficiency of operation.

Of the variables investigated, those concerned with nozzle design have been shown to be of relatively minor importance, giving results peculiar in form, as well as in magnitude, to a specific set of operating conditions. Rate of atomization has been found to be simply related to the variables: metal head, air pressure, metal temperature, and area of metal orifice, when each is considered separately, since linear relationships have been established by the use of very simple functions of these factors. The variables are interdependent, however, and when two or more are considered together the relationships become more complex. A general explanation of the mechanism of operation has been outlined and a tentative equation developed to cover the dependence of rate of atomization upon the most important variables. The principal advantages of the method are given together with a summary of the value of each variable as a means of process control. The determination of the size distribution of the powder of sub-sieve size is described briefly in the Appendix.

I.—INTRODUCTION.

RECENT developments in the use of aluminium powder in a number of industries have made many demands upon the producers of this material, demands accentuated during the war period by the extensive use of aluminium powder as an ingredient of incendiary and explosive compositions. In addition to the high consumption, the uses of the material are so highly diversified that they necessitate the production of powders differing widely in their specific characteristics. Yet of the many methods at present available for the production of metal powders¹ only four are used for aluminium: milling, shotting, granulation, and atomization. Of these, milling produces aluminium in flake form, characterized by its use as a pigment, while shotting and granulation

* Manuscript received 29 January 1947.

† Development Manager, Metals Division, Durham Chemicals, Ltd., Birtley.

give comparatively coarse products of uncertain oxide content. The remaining process, that commonly referred to as atomization, has been found to be of great flexibility with respect to the size distribution of the product, and, surprisingly enough when the underlying mechanism is considered, the oxide content is sufficiently low to permit the production of strong compacts by the normal devices of powder metallurgy.² A certain looseness of terminology exists in the current use of the word "atomization" since it is used to cover methods of metal-powder manufacture differing widely in their characteristics. The word is used here to refer to those processes, the essential principle of which is that a stream of molten metal is disintegrated by a controlled flow of compressed fluid; such a definition would exclude any methods of production of metal powders by mechanical disintegration of molten metal.

The idea of disintegrating a metal stream by a blast of compressed fluid is by no means new,³ in its most elementary form it was the basis of a German patent taken out in 1882, the object being the production of lead powder for use in accumulators. Since that date there has been a steady improvement in both apparatus and technique, the principal trend being towards the development of a compact, self-contained nozzle as opposed to the original independent system. Two American patents⁴ granted in 1924 and 1925 describe, respectively, a system for the atomization of metals and, in more detail, a nozzle for use with this system. The special feature of this nozzle is that the compressed gas issues from an annulus concentric with the metal orifice; this principle has been made the basis of many atomizing nozzles since then and is, indeed, characteristic of the nozzle with which the present work was performed.

Although there is abundant material, particularly patent literature, dealing with the construction of apparatus used for atomization, there appears to have been little or no published work indicating the scope of the process, its advantages over other production methods, or its more practical fundamental aspects. Doubtless this can be ascribed to the many modifications of apparatus which can be employed and the necessarily highly specific character of an investigation dealing with the details of any particular method. Nevertheless, it was felt that reasonably comprehensive tests, concerned with operational conditions and factors of nozzle design as means of control of the characteristics of the final product, might yield useful results and indicate, in at least a general manner, the fundamental factors underlying the process. For comparative purposes, some research was carried out on water spraying as a preliminary to aluminium; the results are included at appropriate

places in the text because of their value in confirming those obtained with metal.

II.—SCOPE OF EXPERIMENTAL WORK.

The object of the research was to determine the effects of certain variable factors upon the nature of the product and the practicability of the method for the production of aluminium powder. It was decided that, under any set of conditions, the results of operation could be defined by three characteristics, so that, in essence, the work comprises a study of the effects of alteration in the variable factors upon these characteristics, viz. productive rate, quality of product, and ease of operation.

1. *Productive Rate.*

Many production methods for metal powders which have proved to be eminently satisfactory on a laboratory or pilot-plant scale have suffered because the rate of output has proved to be prohibitively low when applied on a works scale. Perhaps this has been more commonly experienced with iron powder than with aluminium; nevertheless, the productive rate is of immense importance since it greatly influences the manufacturing costs of the process.

2. *Quality of Product.*

The quality of a metal powder is essentially a composite property, and has several fundamental attributes inevitably associated with it. Of these, there are three which might be considered as primary; others, such as flow factor, apparent density, and pressing properties, which derive from these primary properties, were not therefore investigated.

(a) *Chemical Quality.* Obviously the suitability of a metal powder for a particular requirement is originally governed by conformation to the chemical specification for the material. When relatively pure metal (i.e. as distinct from alloys) is used in powder metallurgy, chemical considerations become almost solely limited to the quantity of oxide present and its mode of distribution; where this is important, reference to it will be found in the text.

(b) *Size Distribution.* Although the fundamental questions of size distribution of any given powder, and their relation to the processing of that powder, are not fully understood, it is nevertheless accepted as one of the most important factors of powder metallurgy and one which exerts considerable influence upon such properties as flow factors and apparent densities. In this work, size distribution was investigated by sieving and by representative sub-sieve size analyses carried out using an air elutriator of simple but effective design (see Appendix).

(c) *General Characteristics.* In this group are included those properties which are rather difficult of quantitative interpretation, such as shape of particles and surface characteristics, properties which almost certainly represent the "unknown factors" in flow, loose packing, and ease of pressing. Atomized particles are generally stated to possess an elongated tear-drop form. In actual practice they are, of course, highly variable in shape (atomized copper powder can be obtained in the form of almost perfect spheres because of the high surface tension of the molten metal), but their mode of formation is such that they are usually elongated, in the case of aluminium generally approximating to an ellipsoid in which the major axis is almost exactly twice that of the smaller dimension. This fact was determined statistically from microscopic measurement of a large number of particles, and was found to hold for all sizes from 36 mesh B.S. sieve (422 microns) down to 10 microns. During the trials, the particle shape showed no systematic change with alteration in any variable; it was felt that investigation of this factor could, therefore, be justifiably eliminated. Characteristically the particles were found to be irregular in outline but superficially smooth (see Figs. 22-25 (Plate XVII)) and appeared to be quite sound, almost completely lacking in large discontinuities such as are found in metal powders produced by certain other methods.

3. *Operational Characteristics.*

Certain conditions connected with the process, which, although permitting brief periods of satisfactory operation, rendered continuous atomization impracticable, were discovered during the trials. Where such conditions have militated against complete accuracy of results, the reason and possible solution have been indicated at the appropriate points in the text.

Owing to the tremendous number of possible combinations, any work which involves the investigation of the effects of a number of variable factors on the characteristics of a general process must necessarily be incomplete. It was decided therefore, in this case, that isolated treatment of each factor, while maintaining all others constant, would yield a representative set of data, sufficient to give at least a general picture of the process mechanism.

III.—APPARATUS.

1. *Layout of Plant.*

When considering erection of plant for the production and collection of even small quantities of aluminium powder, one of the governing

factors is complete observance of all reasonably practical safety precautions.⁵ When dispersed in air aluminium can be dangerously




FIG. 1.—Diagrammatic Representation of Plant Layout.

KEY.

- | | |
|---------------------|---------------------------|
| A. Melting furnace. | E. Explosion vents. |
| B. Atomizing unit. | F. Cyclone. |
| C. Motor. | G. Shut-off slide valve. |
| D. Fan. | H. Off-take rotary valve. |

inflammable⁶; static dust clouds must therefore be strictly avoided at any point in the circuit, and the concentration of powder in suspension should be kept below the explosive limit throughout as great a part of the plant as is practicable. A number of systems for handling aluminium powder are at present in use, and that described below can probably claim safety and efficiency at least equal to any of the others. The principal features and general layout of the experimental plant are shown in Fig. 1.

The metal is originally melted and raised to the requisite temperature in a gas-fired crucible furnace, from which it is transferred to a separate gas-heated crucible to which the atomizing nozzle is attached (Fig. 2). The powder is blown into a large-diameter conveying tube, the mouth of which is encased in $\frac{1}{2}$ -in.




FIG. 2.—Detail of Atomizing Unit.

KEY.

- | |
|----------------------------|
| A. Clay-graphite crucible. |
| B. Gas Burner. |
| C. Compressed-air line. |
| D. Atomizing nozzle. |
| E. Collecting trunking. |

armour plate, and, by virtue of the suction created by a fan, is carried through trunking to a cyclone of conventional design, where the majority of the powder is deposited and continuously collected. A small amount of fine powder is drawn out of the cyclone by the effluent air and is conducted to a water scrubbing tower where it is trapped and carried away as a dilute slurry.

2. Nozzle Design.

During the atomization of aluminium, an operating temperature of about 800° C. is generally employed, and this imposes severe refractory-corrosive conditions on the nozzle material. Trials conducted with common ferrous materials gave highly unsatisfactory results, the rapid




FIG. 3.—Atomizing Nozzle.

formation of FeAl_3 causing irreparable deterioration of the nozzles even special heat-resisting steels lasted only several minutes. Graphite, although giving a slightly longer life, was nevertheless subject to corrosive attack and was mechanically unsatisfactory. Eventually,

a special refractory material was tried and found to be eminently suitable; there appeared to be no corrosive attack, and refractory strength was sufficiently high to withstand any normal treatment required during operation. The essential features of this particular type of nozzle are that the metal stream, issuing from the central orifice, is caught up by an annular blast of atomizing medium (in this case compressed air) concentric with the jet, disintegrated, and expelled from the nozzle as a confined spray of originally molten droplets, which are chilled and solidify at some point distant from the nozzle. Details of nozzle design are shown in Fig. 3, and it will be noted that only the inner nozzle is constructed of refractory material, other parts not in contact with the aluminium being of mild steel.

IV.—EXPERIMENTAL PROCEDURE.

The original metal charged to the melting furnace was virgin aluminium in the form of 50-lb. ingots, the general analysis of which is indicated in Table II. On attaining the requisite temperature, this metal was transferred to the blowing unit and maintained at a constant

head and temperature during atomization. The viscous and highly tenacious oxide skin which inevitably forms on aluminium at elevated temperatures proved highly detrimental to the atomization process, causing partial blockage of the orifice and consequent diminution of metal flow. For this reason, the metal was frequently fluxed and skimmed during atomization. As soon as a steady flow was obtained from the nozzle orifice, i.e. when sufficient head of metal was attained in the bath, the compressed air was applied. Previous tests had proved that air at atmospheric temperature could be used for the atomization of aluminium without causing undue risk of freezing at the nozzle. This fact is perhaps surprising when the details of the process are considered, but the use of such air was adhered to throughout the tests.

Figures given for rates of atomization were obtained from the material delivered at the cyclone. It was appreciated that this introduced a slight error, in that losses throughout the plant were disregarded, but recovery figures showed these losses to be of a low order (approximately 2%) and sufficiently constant to have little serious effect on the accuracy of the results. Previous experiments on water spraying had given highly reproducible results; Table I has been included for the specific purpose of showing that the degree of reproducibility obtained in the atomization of aluminium is also of quite a high order. The discrepancies which do arise can be attributed to the obstruction of the nozzle by particles of oxide, injected to the base of the blowing crucible when metal is transferred to it. These particles, although not causing complete stoppage of the metal flow, cause a considerable diminution, which may not be readily observed. Thus results can be recorded which are not truly typical of the operational conditions. The practical solution of the problem is to probe the nozzle with a rod of slightly smaller diameter than the nozzle bore; if this is done carefully the material causing the obstruction can be pushed into the body of the metal in the crucible, where it has an opportunity to move to the surface. Only by regular probing can the maximum productive rate be assured. During operation, metal temperature was measured at five-minute intervals by a bare immersion Chromel-Alumel thermocouple, previously checked against a standard couple. The temperature could be maintained within $\pm 10^{\circ}$ C. of any desired value.

The problem of representative sampling in this case, as in most others where relatively large quantities of material are handled, was not solved completely satisfactorily. Recourse was made to the use of a conventional sampling "thief", one sample being taken from each 2 cwt. of powder produced; subsequent quartering reduced

the sample to a workable size. Full precautions were taken to avoid segregation and classification, and all tests were performed in triplicate. Sieving analyses were carried out,⁷ using a set of British Standard Specification Fine Test Sieves which had been calibrated microscopically and shown to agree closely with their nominal sizes. It rapidly became obvious that to report, say, 50% of a powder as passing the 200-mesh sieve without further specification of the fine material was highly unsatisfactory, but considerable difficulty was experienced in finding an apparatus suitable for the analysis of

TABLE I.—*Effect of Variation in Metal Head on Rate of Atomization.*

Test Designation.	Metal Head, in.	Temp., ° C.	Rate of Atomization, lb/hr.
A. 1. a.	10 $\frac{1}{2}$	773	415
b.	10 $\frac{1}{2}$	770	412
c.	10 $\frac{1}{2}$	773	409
A. 2. a.	9 $\frac{1}{2}$	760	413
b.	9 $\frac{1}{2}$	765	407
c.	9 $\frac{1}{2}$	770	410
A. 3. a.	7 $\frac{1}{2}$	773	406
b.	7 $\frac{1}{2}$	780	408
c.	7 $\frac{1}{2}$	775	404
A. 4. a.	5 $\frac{1}{2}$	771	403
b.	5 $\frac{1}{2}$	775	400
c.	5 $\frac{1}{2}$	773	400
A. 5. a.	3 $\frac{1}{2}$	773	396
b.	3 $\frac{1}{2}$	773	387
c.	3 $\frac{1}{2}$	775	390

Average values from Table I give the results shown graphically in Fig. 4, and the comparable results obtained with water are shown in Fig. 5.

sub-sieve-size powder. Eventually, determinations of size distribution of material in this range (i.e. finer than 76 microns) were made using a four-tube elutriator described in the Appendix. A further matter affording some difficulty of solution was that of suitable graphical means of representing size distribution. Finally, it was decided that two simple, but nevertheless effective, methods might be employed:

(a) As an indication of the trend of powder quality throughout a series, the percentage weight of powder which passed the 200-mesh sieve (76-micron aperture) was plotted against the variable factor of the series. It can be taken that such a plot indicates the general effect on the fineness of the powder through the series.

(b) The complete picture of the nature of any variations in size-

distribution is afforded by the use of the cumulative percentage oversize plot, which indicates whether a change is merely a general shift towards increased fineness or coarseness, or whether the actual character has changed, e.g. accentuation or diminution of peaks in the curve, introduction of double-peaked distribution, &c.

V.—EXPERIMENTAL RESULTS.

1. Pressure of Metal Head.

(a) *Constant Factors*: metal orifice, $\frac{5}{32}$ in.; air annulus, $\frac{1}{16}$ in.; protrusion, $\frac{1}{4}$ in.; inclination of external sheath, zero; air pressure, 75 lb./in.²; metal temperature, 775° C.




FIG. 4.—Effect of Metal Head on Rate of Atomization.

It will be seen from the graphs of Figs. 4 and 5 that, within a limited range (the limits being imposed by operating conditions), pressure of metal head has but slight effect on the rate of atomization. With water, the change is considerably more marked; as might be expected, a linear relationship exists between productive rate and the square root of water head. The shape of the curve of Fig. 4 (cf. the curves of Fig. 5) suggests that in all probability a similar relationship holds for aluminium but the working range is too short to permit accurate statistical correlation. Nevertheless, it can be said that, qualitatively at least, the results fall into line with theoretical expectations, and it is only in the magnitude of the change that the results are rather divorced from theory. It is perhaps interesting to note that when reduced to the same orifice diameters, aluminium production at 4-in. metal head and rate of atomization of water at 4-in. water head are nearly equal, in spite of the differences in physical characteristics such as specific

gravity and viscosity (aluminium at 4-in. head : 395 lb./hr.; water at 4-in. head : 403 lb./hr.).

In the light of the results obtained for rate of production, it is relatively easy to explain the effect of metal head on the size grading of the resultant powders. Since the air pressure is constant, the quantity of energy available for atomization must also be constant. Further, since the energy required to disintegrate the metal stream to independent particles must be a function of total surface and therefore of particle size, it follows that an increase in the quantity of metal available for atomization must inevitably lead to a decrease in the energy available per unit weight of metal, with consequent increase in the general coarseness of the product. This allows a generalization to




FIG. 5.—Effect of Water Head on Rate of Atomization.

be made which should be verified by succeeding results : if any factor, which does not in itself affect the energy available for atomization, is altered so as to increase the rate of atomization, then there should be a corresponding decrease in the efficiency of atomization; the powder should become coarser. In cases where the actual available energy, or the energy required for disintegration, are altered, then factors appear which may compensate for, or even completely efface, the above effect. In this particular series, there is a definite decrease in atomization efficiency as the head of metal is increased; even the general characteristic, weight of material passing a 200-mesh sieve, shows a steady reduction throughout the series, and the cumulative plot indicates a general shift towards increased particle size. The typical distribution curve, which can be deduced from the cumulative curves of Fig. 6, is characterized by two peaks separated by a minimal trough

at about 80 microns. The major peak occurs at about 25 microns, and is typical of an asymmetric or skew probability distribution; the other peak is less sharply defined, occurring at about 130 microns and falling away smoothly to zero value at a very large particle size.

Operation throughout the series was good, although at the lower heads, particularly $3\frac{1}{2}$ in., difficulty was experienced with excessive injection of dross into the nozzle, and it became necessary to resort to more frequent probing than was the case with the higher heads. In spite of this, however, atomization was generally quite satisfactory down to $3\frac{1}{2}$ -in. head; below this figure the metal issuing from the orifice possessed a very low velocity, and fouling at the nozzle tip was greatly facilitated.

As stated previously in connection with chemical quality of the powder, the only important factor is the quantity of oxide present; this is substantiated by the figures given in Table II. If the assumption, stated

earlier, that the oxide is principally concentrated on the surface of the particles, is true, then it would be expected that with increased fineness of powder the oxide content would increase, owing to the very much greater specific surface. This was tested in a general manner by taking three rather broad sieve groups and determining the quantity of metallic aluminium present in powder from each of the groups; a marked decrease in this constituent was apparent as the fineness increased.




FIG. 6.—Effect of Metal Head on Size Distribution.

It is interesting to note in this connection that it has been shown by Cremer and Cordiano² that superficial oxide envelopes, if not too thick, do not militate seriously against the value of atomized aluminium for fabrication of articles by powder-metallurgical technique; in fact, for such purposes atomized powder is preferred to other forms of comminuted aluminium. Only very slight modifications of normal pressing procedure are required, and in certain cases the slight oxide coating which is inevitably present may be of actual value in the finished pressing, e.g. for grain-size control.

(b) *Spray Form.* Characteristically the spray consists of a conical

TABLE II.—*Composition of Original Aluminium and Aluminium Powders.*

Constituents.	Virgin Aluminium Ingots, %.	Powder A.1.c, %.	Powder A.5.b, %.
Total aluminium	99.3	99.0	99.1
Metallic aluminium	99.0	98.35	98.5
Combined aluminium (by difference)	0.3	0.65	0.6
Zinc	0.05	0.08	0.05
Iron	0.30	0.25	0.30
Copper	0.02	0.03	0.03
Lead	0.01	0.01	0.02
Silicon	0.10	0.10	0.08

TABLE III.—*Effect of Particle Size on Metallic Aluminium Content of Aluminium Powder.*

Group Size.	Metallic Aluminium, %.
+ 44	99.50
85-100	98.52
- 200	96.67

shell, which comes to a focus at about $1\frac{1}{4}$ in. from the tip of the nozzle and then diverges quite regularly. (The position of the focal point naturally varies with operating conditions, but is generally between 1 and $1\frac{1}{2}$ in. from the nozzle tip.) The stream of liquid metal which initially issues from the orifice persists as a jet for a certain distance from the tip and then "fountains" quite abruptly to the periphery of the cone. Since the cone appears to begin at the outer rim of the refractory nozzle, the film of aluminium must actually be drawn back on to this surface, from which it is subsequently expelled to take the conical form typical of the process. Obviously, the air in the vicinity of the nozzle must be in a complex state of turbulence, so that at various points in the field the operative forces will vary considerably, both in magnitude and direction. Probably within the shell there exists a

slight but nevertheless effective positive pressure directed towards the nozzle, while outside the cone the effluent air creates a force directed away from the nozzle. Thus a two-way motion must go on in the shell of the cone, there being an inner stream flowing towards the periphery and also an outer stream in which the particles are moving in exactly the opposite direction and are ejected to the atmosphere (Fig. 7).




FIG. 7.—Diagrammatic Representation of Spray Form.

2. Pressure of Atomizing Medium : Compressed Air.

(a) *Constant Factors* : metal orifice, $\frac{5}{32}$ in.; air annulus, $\frac{1}{16}$ in.; protrusion, $\frac{1}{4}$ in.; inclination of external sheath, zero; metal head, $9\frac{1}{2}$ in.; metal temperature, 775° C.; volume of free air through nozzle, 250 ft.³/min.

From the early results it appeared that a direct linear relationship existed between air pressure (i.e. gauge line pressure) and rate of atomization, but closer examination revealed that the points actually lie on a smooth curve, as shown in Fig. 8. Fig. 9 shows that, in a series of curves at different heads, relating rate of atomization and air pressure, as the head is increased the curves approximate more




FIG. 8.—Effect of Air Pressure on Rate of Atomization of Aluminium.

closely to straight lines of decreasing slope, until at large heads it appears probable that alteration in air pressure will cause no change in rate of atomization. Therefore, it follows that the effluence of the compressed air from the annulus produces a force which acts upon the metal stream and imparts to it a greater velocity of flow through the orifice. In the previous section, it was shown that immediately in front of the nozzle

there must exist a slight force, due to the compressed air, directed towards the nozzle. The fact that the results of this series show that there must be a force directed away from the nozzle must at first sight appear anomalous, but it is feasible that these forces operate at quite different points within the field, and can therefore exert an effect simultaneously. A further fact revealed by the curves of Fig. 9 is that the force exerted by the compressed air on the effluent liquid is not constant, but depends upon the head of liquid causing flow. Thus the increase in rate of atomization effected by increasing the air pressure from 0 to 100 lb./in.²




FIG. 9.—Effect of Air Pressure on Rate of Atomization.

becomes progressively less as the head alters from 2 to 24 in. Since at constant head the force due to the head of liquid cannot be affected by alteration in air pressure, it follows that any variations which do occur must be due to changes in the magnitude of the force caused by the compressed air.

Momentarily considering only isolated series at fixed heads, it has been found that a relationship similar to that between liquid head and rate of atomization exists, i.e. the rate is directly proportional to the square root of the air pressure, and not to the air pressure itself. In conformity with the previous series, this suggests that the velocity of the effluent air, and not the actual gauge line pressure, is the controlling

factor. The application of this explanation is extended in the discussion of the results.

Such conditions render it rather difficult to predict the effect of change in air pressure upon the fineness of the resultant powder. In the simple case where the rate of flow is increased without altering the conditions of atomization, it has been shown that there is a coarsening of the product; but in this case there is a compensatory factor, in that any increase in air pressure gives a greater available energy, and thus the final effect will be governed by the relative magnitudes of these two factors. Castleman,⁸ engaged on work of a similar nature but different in application, has suggested that particle size should decrease as the air pressure increases. In this particular case, the results obtained are shown in Fig. 10, and it will be appreciated that the shape of the




FIG. 10.—Effect of Air Pressure on Size Distribution.

curve does not lend itself to simple interpretation. The fact has been substantiated, however, by more recent work on other metals, i.e. increased air pressure causes an increase in fineness up to a maximum, after which there is no further increase; in some cases there may actually be a decrease. It is feasible that a maximum may occur on

the fineness curve if that curve is the resultant of two opposing curves one indicating an increase due to the increased air velocity, the other a decrease due to the increased flow of metal. The average oxid content of the powder showed only a slight increase throughout the series, and it is probable that this is merely due to the increased quantity of fines, and therefore increased surface area. The difference in combined aluminium contents between the 30 and 90 lb./in.² product was of the order of 0.75%.

3. *Protrusion of Inner Refractory Nozzle.*

(a) *Constant Factors:* metal orifice, $\frac{5}{32}$ in.; air annulus, $\frac{1}{16}$ in. inclination of external sheath, zero; air pressure, 75 lb./in.²; metal head, $9\frac{1}{2}$ in.; metal temperature, 775° C.

Reference to Figs. 3 and 7 will make clear the implied meaning of the term "protrusion". It is an actual measurement of the length of the refractory nozzle which is not encased by the outer sheath, and obviously controls the point at which the compressed air impinges upon the metal stream.

The results obtained in the water spraying were considered originally to be rather anomalous, the minimal trough being particularly difficult to interpret. However, the results obtained in the aluminium atomization are similar in nature; the absence of the minimal trough might be due to some difference in nozzle design, or, more probably, either the position of the trough or its magnitude is sufficiently different from that of water for it not to be shown on the curve within the experimental range. In general, the fact that there is a definite maximum on the curve is not surprising if it is considered that protrusion has a two-fold effect:

(i) As protrusion is increased, the direction of flow of the effluent air becomes more nearly collinear with that of the metal jet, and therefore the tractive component of the force acting on the metal becomes greater. (This is accompanied by an increase in the "focal length" of the metal cone.)

(ii) As protrusion increases, the point of application of the compressed air becomes further removed from the point of initial emergence, and therefore the energy available for atomization must be reduced by a purely dissipative effect, which would mean a decrease in the force applied to the metal.

Unfortunately, the subject does not lend itself to more rigorous treatment, but it is quite conceivable that, at a certain value for protrusion, the loss due to dissipation more than compensates for the





FIG. 22.—Aluminium Powder, 60/72 Mesh. $\times 27$.

FIG. 23.—Aluminium Powder, 170/200 Mesh. $\times 27$.

FIG. 24.—Aluminium Powder. Elutriator fraction for tube 1 after 2 min. separation. $\times 75$.

FIG. 25.—Aluminium Powder. Elutriator fraction for tube 1 after 40 min. separation. $\times 75$.



increased value of the component force, and if protrusion is increased further there must be a steady reduction in the magnitude of the tractive force and corresponding reduction in the rate of flow.




FIG. 11.




FIG. 12.

FIG. 11.—Effect of Protrusion on Rate of Atomization of Aluminium.

FIG. 12.—Effect of Protrusion on Rate of Atomization of Water.




FIG. 13.—Effect of Protrusion on Size Distribution.

The curve shown in Fig. 13, relating protrusion and percentage of "fines", is interesting in that it is the direct reverse of that for protrusion and rate of production (Fig. 11). Thus the fines are at a

maximum at low protrusions, fall rapidly to a minimum, and then rise gradually, as the protrusion increases, to a relatively high value. It is justifiable to assume that, except at high protrusions, where the dissipative effect will be marked, alteration in protrusion will have no great effect upon the actual atomization, and therefore changes in atomization efficiency will be conditioned almost solely by changes in rate of flow. (This, of course, is in agreement with the earlier statement on inter-relation of flow rate and efficiency of atomization.)

Difficulty of operation imposed a lower limit to the series, for, while zero protrusion was quite feasible when atomizing water, with aluminium it was found that even at $\frac{1}{8}$ -in. protrusion operating conditions became difficult, owing to the effluent metal fouling the air annulus; and at zero protrusion atomization was quite impracticable. At the other end of the scale, operation was quite satisfactory even at the high protrusion of 1 in.

4. Orifice Area.

(a) *Constant Factors*: air annulus, $\frac{1}{16}$ in.; protrusion, $\frac{1}{4}$ in.; inclination of external sheath, zero; air pressure, 75 lb./in.²; metal temperature, 775° C.




FIG. 14.

FIG. 14.—Effect of Orifice Area on Rate of Atomization of Aluminium.




FIG. 15.

FIG. 15.—Effect of Orifice Area on Rate of Atomization of Water.

The effect of alteration in area of metal orifice is quite clearly shown in the curves of Figs. 14 and 15, from which it is obvious that a marked linear relationship exists between rate of flow and area of

orifice, for both water and aluminium. Only at very low diameters is it possible that any deviation exists, since at such diameters the effects of wall friction might become of sufficient importance to cause an appreciable alteration in the velocity of flow through the orifice. However justifiable this may be theoretically, in practice its effect is negligible. Since alteration in the orifice area does not in itself change the conditions of atomization, any variation in size distribution can only be considered as a secondary effect, i.e. as a consequence of the altered metal flow. Therefore, since there is a definite quantity of energy available for atomization, it is probable that the fineness of the product




FIG. 16.—Effect of Metal Orifice on Size Distribution.

will decrease in a regular manner. Fig. 16 shows this to be true, and also that fineness actually changes linearly with orifice area.

One operational characteristic which had not been noted previously was observed during this series, particularly at the higher end of the scale where rates of atomization were of the order of 1000 lb./hr. It is well known that metal particles will bond together quite strongly if pressure is applied to them, even at atmospheric temperature. It is, perhaps, not so fully appreciated that metal powders will sinter, or adhere together strongly, at elevated temperatures below their melting points, in the absence of any external applied pressure. An example of this particle cohesion under the influence of temperature was observed during the blowing tests conducted in this series. At high rates of atomization, large "growths" occurred in the pipe-line into which the powder was initially blown. These growths commenced some 6 ft. from the mouth and on the floor of the pipe-line, grew to the central

axis of the pipe, and then increased in length towards the nozzle, frequently attaining a length of about 5 ft., with a diameter of 2 ft. at the base. In the earlier stages of formation, it is quite definite that the individual particles were not molten when they joined the mass, since the typically atomized form of each particle was retained in the final, coherent body, and yet the strength of the deposit was frequently great enough to resist manual disintegration. Such growths naturally had a serious effect on the accuracy of the results, and for this reason short running periods and frequent cleaning had to be resorted to during the tests at large orifice areas.

5. Angular Inclination of External Sheath.

(a) *Constant Factors*: metal orifice, $\frac{7}{32}$ in.; air annulus $\frac{1}{16}$ in.; protrusion, $\frac{1}{4}$ in.; air pressure, 75 lb./in.²; metal temperature, 775° C.

This factor, which is purely one of nozzle design, has effects similar to, and is comparable with, one previously discussed, namely protrusion




FIG. 17.




FIG. 18.

FIG. 17.—Effect of Sheath Inclination on Rate of Atomization of Aluminium.

FIG. 18.—Effect of Sheath Inclination on Rate of Atomization of Water.

of the inner refractory nozzle. Obviously, any increase in the angular inclination of the external sheath inevitably means that the air stream is made to converge more rapidly, whereas increase in protrusion has a reverse effect, giving a greater degree of divergence. Owing to the turbulence existing in the region adjacent to the nozzle tip, it is not feasible to make any strict geometrical comparison between the two factors, but examination of Figs. 11 and 17 shows that the general

relationship outlined above does exist, i.e. the graph relating rate of atomization and decreasing inclination of external sheath could almost be superimposed on that of rate of atomization and protrusion.

It is a rather surprising fact that the maximum point on both the curves (i.e. for aluminium and for water) occurs at approximately 45° sheath inclination; indeed, on consideration, it is strange that any maximum should occur at all. On purely theoretical grounds, it would be expected that the productive rate would show a continuous reduction in magnitude as the convergence of the air stream became more pronounced, since the horizontal, tractive component of the force exerted by the air on the metal would steadily decrease. The effect of altered sheath inclination upon size distribution was also rather unaccountable, for the only tendency which was observed, and that only to a very small degree, was towards a slight increase in fineness as inclination increased; but the differences were so small as to be almost within the limits of experimental error. It is feasible, however, that increase in the angle of impact of the air and metal streams will alter the actual atomization and probably render it less efficient. Such an effect would be offset by the decreased production, so that a balance might be effected between the two, giving very little change in the resultant size distribution. Operationally, high angles of inclination were found to be unsatisfactory, giving a much more divergent spray and aggravated "side-splashing".

6. *Metal Temperature.*

(a) *Constant Factors*: metal orifice, $\frac{5}{32}$ in.; air annulus, $\frac{1}{16}$ in.; protrusion, $\frac{1}{4}$ in.; sheath inclination, $\frac{1}{4}$ in.; air pressure, 75 lb./in.².

The variable factors investigated previously have exerted what might be termed an external effect on the process, but this represents something quite different, in that the resistance of the metal to atomization must inevitably be altered by any changes in temperature. The metal property which exerts most control over the process will obviously be surface tension, with viscosity as a factor of secondary importance. By comparison with normal liquids, it may be assumed that, for liquid metals over short ranges of temperature, both surface tension and viscosity are inversely proportional to temperature, and therefore the resistance to disruption must also decrease with increased temperature. Fig. 19 shows, however, that the exact reverse of this occurs, and that there is a steady reduction in rate of production as the temperature of the metal is increased. The explanation of this apparent anomaly is not difficult to find. The process of atomization, as carried out with this type of nozzle, is not characterized by the weight of metal

flowing through the orifice, but by the volume, a characteristic which is readily affected by alterations in temperature. From this, it will be appreciated that, as the temperature of the metal is increased, the actual volume of metal passing the orifice will not be changed (this ignores viscosity fluctuations), but the resultant mass will be considerably less than that obtained at lower temperatures. Since all rates of atomization are reported in units of mass, it is obvious that there will be a decrease in mass rate of atomization with temperature, a decrease which will be slightly modified by the simultaneous effect of




FIG. 19.—Effect of Metal Temperature on Rate of Atomization.

temperature changes upon viscosity, but which should, nevertheless, be linear, since cubical expansion of the metal and viscosity are, respectively, direct and inverse linear functions of temperature. In the case of degree of atomization, the effects of temperature on surface tension become of considerable importance, since it is the magnitude of the forces of surface tension which primarily governs the size of the original liquid droplets, into which the mass of metal is disintegrated. Therefore, if the temperature of the metal is increased, the surface tension is decreased and the available energy can effect more complete breakdown of the stream, giving liquid droplets smaller in size than those obtained at lower temperatures. Further, the droplets are initially at a higher temperature and therefore pass through a greater thermal range before reaching room temperature; they consequently suffer a greater reduction in volume than corresponding "low-temperature"

particles. As a result of these two factors, it is to be expected that the general fineness of the powder will increase throughout the series in a regular, probably linear, manner. The two factors which exert the most influence upon particle shape will be temperature at time of formation and time interval between formation and solidification. If the temperature of the metal is increased, the magnitude of the forces




FIG. 20.—Effect of Metal Temperature on Size Distribution.

of surface tension will be less at the actual moment of drop formation, which would give a tendency to reduced sphericity. To compensate for this, however, there is the increased period during which the particles remain liquid, so that the slightly reduced forces have a longer time in which to affect particle shape. Examination of the powders produced throughout this series revealed no appreciable change in particle shape; the 2 : 1 major- to minor-axis ratio was maintained, even at the highest temperature.

VI.—DISCUSSION OF RESULTS.

Castleman⁸ has attempted to give an analysis of the process of atomization (particularly as applied in internal-combustion engines), based on Rayleigh's work relating to the instability of liquid columns.⁹ Although Castleman's derivations cannot be directly applied to this work, the general theory certainly can, since conditions are quite comparable in both cases. His major assumption, that, unless the air velocity is exceedingly high, atomization proceeds by a process of ligament formation, appears quite sound, and is in accordance with known facts. Thus the ultimate particles are not produced directly

from the main body of liquid, but are formed as a result of the collapse of elongated ligaments torn from the main mass by the external air stream. The size of the ultimate particles is determined by the initial diameters of the ligaments, which for any given liquid are simply a function of the velocity of the surrounding atomizing medium, the diameter and life of any ligament decreasing with increased air speed.

In the atomization of aluminium, the rate of atomization is completely determined by the rate of flow of metal through the orifice. Since exhaustive mathematical treatment would be impracticable, the only operative forces will be considered to be the pressure of metal head in the crucible and the tractive force applied to the metal by the emergent compressed air. (Whether this tractive force is a resultant of several forces due to the compressed air or not has no material effect upon the analysis.) Superficially, it would appear that these two forces are distinct and in no way related, but this is not true. The curves shown in Fig. 5 indicate that, at any given pressure, the relationship between head and rate of atomization can be expressed by an equation of the type :

$$R = a\sqrt{H} + b \quad . \quad . \quad . \quad . \quad . \quad (1)$$

where R is the rate of atomization in lb./hr.; H is the head, in inches; and a and b are constants.

Similarly, at any given head, the rate of production is proportional to the square root of the air pressure, and the two factors are related by the general equation :

$$R = c\sqrt{P} + d \quad . \quad . \quad . \quad . \quad . \quad (2)$$

Thus, assuming the variables to be completely independent, combination of equations (1) and (2), to render them more broadly applicable, would yield an equation of the form :

$$R^2 = K.H.P + K_1 \quad . \quad . \quad . \quad . \quad . \quad (3)$$

This equation cannot be correct, however, since it demands that dR/dP increases with H , when actually the reverse is required (see Fig. 9). This is perhaps obvious when it is considered that the variables cannot be independent, since the magnitude of the tractive force due to the compressed air is determined by the velocity of the air relative to that of the metal and not by the simple air velocity.

Thus, the true equation must be of the type :

$$R = f\{H\} + (f\{P\} - f_1\{H\}) \quad . \quad . \quad . \quad . \quad (4)$$

where (i) $f\{H\}$ is some function of head which accounts for the increase of R with H at fixed values of P (probably $f\{H\} = K\sqrt{H}$); (ii) $(f\{P\} - f_1\{H\})$ is a composite term involving functions of P and H so

that the whole term allows for the decrease in magnitude of dR/dP as H increases, i.e. the whole term is essentially a function of the relative velocity of air to metal in the immediate vicinity of the nozzle tip.

Obviously it is possible to visualize a state where velocities are equal and the metal stream moves inside a cylindrical shell of air without any actual atomization occurring. Further, if the effluent velocity of the liquid is very high compared with that of the air, conditions are altered so that they become comparable with those which obtain during pressure atomization or the so-called "airless" injection.

It was appreciated at the outset that graphic presentation of size data offered several difficulties which would not be solved by the use of




FIG. 21.—Nature of Size Distribution of Atomized Aluminium.

curves showing the effect of variation of a factor of process control upon the weight percentage of powder passing a 200-mesh sieve, but, nevertheless, its general value was considered to be sufficient to justify its use. In the case of increasing metal head at constant air pressure, it has been shown that the most important consequences are that the rate of metal flow is increased, and because of this the velocity of the air relative to the metal is decreased, both of which factors lead to increased particle size. This is shown in Fig. 6, and with reference to the cumulative oversize plot it is interesting to note that the characteristic distribution curve is not that of the usual skew-probability type, but exhibits two peaks, the major one occurring at approximately 30 microns and the other at approximately 120 microns (see Fig. 21). It is felt that this is an essential characteristic of the process and is due

to the fact that the material distribution within the spray is not uniform, but is affected by the gravitational force exerted on the metal as it leaves the orifice. Thus, the metal stream is not truly concentric with the effluent compressed air, but is inclined towards the lower part of the surrounding cone, with the result that two separate sets of conditions operate simultaneously, and that the distribution curve shown in Fig. 21 (b) is actually the resultant of two curves. This is substantiated by the fact that powder resulting from atomization in a vertical plane (i.e. either upwards or downwards) where there is complete symmetry, usually exhibits a simple asymmetric or skew-probability distribution in the "as-blown" condition.

When considering the effects of alteration in air pressure upon the size grading of the product, it is necessary to remember that several processes operate simultaneously. When the air pressure is increased, there is an automatic increase in atomization efficiency, but there is also an increase in the quantity of material available for atomization; and these two factors, to a certain extent, oppose each other, the resultant effect depending upon their relative magnitudes and relative rates of change. It is conceivable that, above a certain pressure, the increased coarseness due to an increase in the quantity of metal flowing becomes greater than the refinement due to the increased air velocity. Such an explanation accounts for the maximum which occurs in Fig. 10 and the subsequent slight decrease in fineness at air pressures above 50 lb./in.².

The two factors, protrusion of inner nozzle and angular inclination of external sheath, investigated in Part V (sections 3 and 5), are rather similar in nature, as has been indicated earlier, and it is considered that the explanations developed in section 3 adequately account for what at first sight may appear to be anomalous results. Thus, as the protrusion is increased, the point of application of the compressed air to the metal stream is moved further from the point of emergence of the compressed air, so that its velocity, which has been shown to be the important factor, is considerably less than the original effluent velocity. The immediate result of such conditions would be a steady decrease in the rate of flow through the nozzle, but initially there is a strong compensatory factor, a consequence of nozzle design, in that a slight protrusion prevents the highly undesirable buffering action of the compressed air in the immediate vicinity of the nozzle tip, and aligns the flow of the air more completely with that of the metal stream. At a particular value for protrusion, the decrease due to the reduction in velocity becomes greater than the preventive action of the increased protrusion, and as the protrusion is increased beyond this figure so the rate of flow

suffers a corresponding decrease. Since the effects of increased protrusion upon fineness are directly opposite to those relating to rate of atomization, it appears that, within the experimental limits, fineness of product is conditioned to a very considerable extent by changes in rate of flow brought about by increased protrusions (cf. Figs. 11 and 13). The results obtained for the series concerned with the inclination of the external sheath (this in effect means the inclination of the effluent air) do not lend themselves readily to interpretation, since there would not appear to be any factor capable of causing a sudden change in the rate of production as the value for sheath inclination reaches approximately 45° .

It was appreciated that the size of the orifice would exert considerable influence on the process, and it can be said that it is the most important controlling factor in the whole process, mainly because of the magnitude of the changes in rate of production and quality of powder brought about by any alteration in the diameter of the nozzle orifice. The flow of metal through the orifice is governed by two factors, the velocity of the metal and the cross-sectional area of the orifice, and although alteration in area must have some effect upon the frictional losses throughout the system, it is probably safe to assume that, within the limits of the working range, alterations in the area of the orifice have but little effect upon the mean velocity through the orifice. Theoretically, therefore, changes in area mean a corresponding and predictable change in the rate of flow or atomization. That such conditions are not completely attained in practice is indicated by the fact that the theoretical curve cannot be superimposed completely upon the curve obtained experimentally, but the discrepancies are only relatively slight. Further, since the conditions of atomization are not affected directly, apparent changes in efficiency of atomization will be due solely to variations in the quantity of metal available for atomization.

In addition to this obvious effect, there is an important connection between orifice area and efficiency of operation. It was stated earlier that throughout the tests air at atmospheric temperature was to be employed, and this proved quite satisfactory until attempts were made to operate with relatively small orifices of the order of $\frac{1}{8}$ -in. diameter. At such low values, it was found that the rate of flow of metal was too small to counteract the abstraction of heat from the body of the nozzle by the air passing through the annulus, with the inevitable consequence that freezing at the nozzle tip became so frequent as to render continuous operation impracticable. This difficulty was solved by preheating the air prior to its entry into the nozzle, thus permitting smaller orifices to

be employed, giving a considerable improvement in fineness. Isolated tests, combining the use of preheated air and small bores, have been performed, and powder passing more than 90% by weight through a 240-mesh sieve has been readily produced at a rate of approximately 1 cwt./hr.

In magnitude of effect, metal temperature is the variable next in importance to orifice area, and, like that factor, its effects are relatively straightforward and applicable over wide ranges of conditions. That is, no matter what combinations of nozzle design, metal head, air pressure, and metal orifice are used, it is highly probable that linear relationships will exist between temperature and rate of flow and quality of product because of the fundamental character of the relationships. With respect to rate of production, such conditions will also prevail for metal head, air pressure, and metal orifice, but the nature of the results of variation in the other factors (i.e. sheath inclination and protrusion) will be much more affected by alteration in the remaining controlling factors. Reverting to considerations of metal temperature, there must obviously be a lower limit of temperature for satisfactory operation, but this limit varies considerably with other conditions, particularly temperature and pressure of the atomizing medium. These conditions govern the rate of heat abstraction, and the area of the orifice, in conjunction with metal temperature, control the amount of heat given up to the body of the nozzle. With an orifice of $\frac{5}{32}$ in. dia. and air at 75 lb./in.² at atmospheric temperature, the lower limit of operation was found to be about 720° C., at which temperature periodic freezing occurred, rendering the process intermittent in operation.

Although the data available are insufficient to allow the rate of atomization to be expressed as a specific function of the primary control variables (i.e. metal head, air pressure, metal orifice, and metal temperature), adequate information has been derived to allow a general relationship to be established. Thus, the relationship between rate of production and air pressure and metal head has been considered to be covered by equation (4):

$$R = f\{H\} + (f\{P\} - f_1\{H\}) \quad . \quad . \quad . \quad (4)$$

Introducing the variables, area of metal orifice and metal temperature, into equation (4) gives the general equation:

$$R = \frac{K.A}{T} [f\{H\} + (f\{P\} - f_1\{H\})] \quad . \quad . \quad . \quad (5)$$

where R is the rate of metal flow; A is the cross-sectional area of metal

orifice; T is the metal temperature, and is a variable of limited applicability (i.e. becoming invalid at the minimum temperature for satisfactory atomization, and also at the boiling point of the metal); H is the metal head; and $(f\{P\} - f_1\{H\})$ is a composite term covering relative velocity of air to metal (see p. 124).

Although certain of the results lend themselves to more definite mathematical treatment (e.g. metal temperature and orifice), it would not be of any advantage to make equation (5) any more specific in application for these particular variables while factors such as protrusion and sheath inclination can be discussed only in very general terms.

VII.—CONCLUSIONS.

The process of atomization which has been described is highly suitable for the production of good-quality aluminium powder of either a coarse grade, such as 36/dust, or a relatively fine grade, such as 200/dust. The rate of atomization is not constant, but is governed by the size distribution required in the final product, and in this connection it has been found that, as a general rule, any increase in rate of flow is inevitably accompanied by a decrease in the fineness of the resultant powder. Nevertheless, the productive rate is high when compared with other processes, and although it is difficult to produce 200/dust powder at a rate of more than 1 cwt./hr., a rate of 6-7 cwt./hr. can readily be maintained on standard 36/dust powder. Operation can be brought to a high pitch of efficiency, ultimate losses being approximately 3% during the production of material passing 50-60% through a 200-mesh screen.

The powder produced by this process is of high quality. Oxidation of the powder is in no degree excessive, and for metallurgical (i.e. pressing and sintering) and explosive uses the powder has been found to be eminently satisfactory. Contamination by other materials during production is very limited; slight dissolution of iron is caused by using steel ladles for transmission to the blowing crucible, but this factor, were it to become serious, could be readily overcome. Particle shape is surprisingly uniform, the length of each particle being approximately twice as great as the other dimensions, and this "shape factor" is probably a general constant, typical of any specific metal powder produced by this process.

Control of the size characteristics of the product is achieved by alteration of several process variables, the most important of which are metal head, air pressure, metal temperature, and metal orifice. In summary, the effects of increasing these variables are :

(i) *Metal Head* : Slight increase in rate of atomization. Corresponding decrease in fineness of product.

(ii) *Air Pressure* : Steady increase in rate of production. Increase in fineness up to 50 lb./in.², thereafter a slight decrease.

(iii) *Metal Temperature* : Strongly marked linear decrease in rate of production (about 1 lb./hr./° C.). Corresponding linear increase in fineness.

(iv) *Area of Metal Orifice* : Linear increase in rate of production up to very high values (1200 lb./hr. at 0.079 in.² area). Corresponding linear decrease in fineness.

In magnitude, the effects of none of the variables compare with those deriving from alteration in the area of the metal orifice. In practice, alteration in this factor is employed to effect the major adjustments in size distribution which are required, and other variables are only altered to bring about further slight modifications necessary to bring the material within specification. Subsidiary variables, such as protrusion of inner nozzle and inclination of external sheath, effect such relatively small changes that they are unsatisfactory as means of process control, but may conveniently be employed in certain particular circumstances.

ACKNOWLEDGEMENTS.

The investigation was carried out at the works of Durham Chemicals, Ltd., Birtley, and the Department of Metallurgy, King's College, Newcastle-upon-Tyne. The author is indebted to Professor C. E. Pearson of King's College for many valuable suggestions during the course of the study, and to the directors of Durham Chemicals, Ltd., for permission to publish the results.

REFERENCES.

1. J. C. Chaston, *Elect. Commun.*, 1935, **14**, (1), 133.
2. G. D. Cremer and J. J. Cordiano, *Trans. Amer. Inst. Min. Met. Eng.*, 1943, **152**, 152.
3. T. H. Turner and N. F. Budgen, "Metal Spraying". London : 1926 (Griffin and Company, Ltd.).
4. E. J. Hall, U.S. Patents No. 1,501,449 and 1,545,253.
5. Fire Offices' Committee, "Code of Precautions Recommended for Aluminium-Powder Factories". London : 1945.
6. I. Hartmann, J. Nagy, and H. R. Brown, *U.S. Bur. Mines Rep. Invest.*, 1943, (3722), 44 pp.
7. "British Standard Specification for Test Sieves." (B.S. 410). London : 1943.
8. R. A. Castleman, *J. Research Nat. Bur. Stand.*, 1931, **6**, 369.
9. Lord Rayleigh, *Proc. Lond. Math. Soc.*, 1879, **10**, 4.
10. H. E. T. Haultain, *Trans. Canad. Inst. Min. Met.*, 1937, **40**, 232.
11. P. S. Roller, *Proc. Amer. Soc. Test. Mat.*, 1932, **32**, 607.

APPENDIX.

SIZE GRADING OF SUB-SIEVE-SIZE POWDER BY AIR ELUTRIATION.

The accurate classification of powders of sub-sieve sizes is a problem which has received attention from investigators in all the fields concerned with the handling and treatment of finely particulate matter. Although all the methods which can be applied must ultimately be dependent upon microscopic calibration, certain of the standard methods suffer through lack of reproducibility in results, which renders them unsuitable for either routine sizing tests or for more accurate research work. Most of the methods which can be applied to particles in the 1-100 micron range have been tried in connection with this work, and, of these, only air elutriation, which is not strictly dependent upon any fundamental law, was found to give satisfactorily reproducible results in a relatively short time.

The majority of the earlier methods employed for size determination belonged to that class now commonly referred to as "sedimentation methods", and are typically dependent upon Stokes' Law relating to the unhindered fall of solid particles in homogeneous fluids. The technique of elutriation is essentially the reverse of sedimentation, in that it depends upon the provision, in a fluid medium, of velocities greater than the ultimate free falling velocity of certain of the particles under the given conditions of test. Further, in elutriation, conditions are such that the fluid medium is in a state of considerable turbulence, which renders Stokes' Law inapplicable except as a very approximate basis for calculation.

The most interesting apparatus which have been developed of recent years are those due to Haultain¹⁰ and Roller,¹¹ similar in both principle and design, and apparently efficient and accurate in operation. For the sizing of aluminium powder, preliminary tests indicated that air elutriation afforded a satisfactory method, and an apparatus was devised which, although similar to both the Haultain Infra-Sizer and the Roller Air-Analyser in design, differed from them in certain respects, and was, in general, simpler in operation. The elutriator consisted of four glass tubes, connected in series to a regulated supply of compressed air. The tubes increased progressively in size, and the effluent from the largest was led to a bag filtration unit. The air inlet, at the base of each tube, was designed so that maximum agitation of the powder was obtained. Extensive calibration tests showed conclusively that, even with this relatively simple apparatus, results reproducible to within $\pm 2\%$ could be obtained within 40 min., with the additional

advantage that the grades of powder are available, if required, for further physical or chemical examination. The efficiency of separation obtainable with the instrument can readily be appreciated from Figs. 24 and 25 (Plate XVII), which are comparative photomicrographs of fractions produced after different times of elutriation.

THE SURFACE TENSION AND DENSITY 1115 OF LEAD-ANTIMONY AND CADMIUM- ANTIMONY ALLOYS.*

By H. T. GREENAWAY,† B.Met.E.

SYNOPSIS.

This paper describes the first part of a programme of research on several aspects of the surface tension of liquid metals and alloys, including the significance of this property in casting and soldering. The work of earlier investigators is briefly reviewed, and a description is given of the construction and checking of the maximum-bubble-pressure apparatus which was selected for use.

Using vacuum-distilled mercury and water as standard liquids, and values obtained by previous workers as a basis for comparison, the equipment and technique have been proved to give consistent and reliable results.

The surface tensions of molten cadmium-antimony and lead-antimony alloys have been determined; the curves of surface tension plotted against composition show a large fall for the cadmium-antimony system, which contains a solid intermetallic compound, but only a small fall for the lead-antimony system, in which no solid intermetallic compound occurs. This finding is in conformity with those of other investigators.

A simple, accurate method has been developed for measuring the densities of molten alloys, using a variation of the maximum-bubble-pressure method employed for the determination of surface tension.

I.—INTRODUCTION.

A GENERAL investigation of the measurement of the surface tensions of liquid metals and alloys has been undertaken because it is considered that the data obtained will have considerable practical and theoretical significance in certain metallurgical operations involving liquid metals and alloys. For example, surface tension is considered to be important in determining the ability of liquid metals and alloys to be cast into intricate shapes and small sections. Likewise, the spreading of solders is governed by a balance of interfacial tensions. On the theoretical side, the existence of intermetallic compounds in liquid alloys is likely to be revealed by an analysis of the relationship between composition and surface tension.

The work described in this paper was also undertaken to correlate the surface-tension-composition relationship in liquid alloy systems with the presence of intermetallic compounds in the solid systems.

* Manuscript received 28 November 1946.

† An officer of Broken Hill Associated Smelters Pty., Ltd., on loan to the Council for Scientific and Industrial Research, Division of Industrial Chemistry, Melbourne, Australia.

Two metal systems were therefore chosen—one (cadmium–antimony) containing a solid intermetallic compound, and one (lead–antimony) containing no solid intermetallic compound—and their surface-tension–composition relationship established.

A comprehensive survey (up to 1935) of the methods employed by various investigators working on the surface tension of liquid metals and alloys is given by Bircumshaw¹ and will not be repeated in this paper.

Sugden² has shown that Macleod's³ "constant" $\gamma^{\frac{1}{2}}/(D-d)$ (where γ is the surface tension in dynes/cm., D the density of the liquid, and d that of the vapour) is constant over large ranges of temperature for a large number of non-associated organic liquids, but increases with temperature for associated organic liquids. Bircumshaw,¹ assuming that Sugden's findings would apply to liquid metals, has shown that tin, lead, bismuth, cadmium, and antimony are all associated in the liquid state.

Matsuyama⁴ observed changes of gradient in the curves of surface tension plotted against composition for the systems cadmium–antimony and zinc–antimony at the compositions of the solid intermetallic compounds known to exist in these alloy systems. The curves also showed a large fall from linearity. On the other hand, the curve for the lead–antimony alloy system (which contains no solid intermetallic compound) showed only a slight fall. From these results he concluded that an intermetallic compound existing in the solid phase does not decompose during melting, and exists as such in the liquid phase.

Sauerwald and Drath⁵ obtained similar results in that the systems bismuth–tin and bismuth–lead, which contain no intermetallic compound, showed comparatively small falls in the curves of surface tension plotted against composition, while the systems copper–antimony and copper–tin, containing one or more intermetallic compounds, gave large falls. They found also that copper and cast-iron melts show a positive temperature coefficient of surface tension.

II.—APPARATUS AND GENERAL TECHNIQUE.

1. *Surface-Tension Determinations.*

The differential maximum-bubble-pressure method was chosen for use in the present investigation because of the formation of a fresh surface with each bubble, independence of angle of contact, and easy temperature control.

Fig. 1 shows the concentric tubes, the stand used to hold them

vertically, and the means employed to melt the metal or alloy under test. The dimensions of the concentric tubes are given in Table I.

In the preliminary tests, both hydrogen and nitrogen were used. The commercial gases were deoxidized by passing through heated fine copper turnings and dried with calcium chloride and phosphorus pentoxide. The rate of flow of gas was adjusted to approximately




FIG. 1.—Surface-Tension Apparatus.

KEY.

- | | |
|---|-------------------------------------|
| A. Inner tube. | K. Tripod stand. |
| B. Outer tube. | L. Levelling screws. |
| C and D. Cocks. | M. Electric resistance furnace. |
| E. Stud. | N. No. 2 Morgan Battersea crucible. |
| F. Spring. | O. Asbestos cover. |
| G. Plunger. | P. Chromel-Alumel thermocouple. |
| H. Mild-steel block. | |
| J. Mild-steel block with V-groove to accommodate B. | |

1 bubble per min. Pressures were measured on a 2 mm.-bore water manometer, a cathetometer reading to 0.001 cm. being used to obtain accurate values.

The effect of various degrees of polish on the ends of the silica tubes was investigated, the following being used as final polishing media: (1) Oakey's No. 120 carborundum paper, (2) Oakey's No. 400 carborundum paper, and (3) +5 to -15 μ aloxite abrasive on a wet polishing cloth.

The method employed to calculate surface tension from the observed

maximum bubble pressures was the method of successive approximations developed by Sugden.⁶ The calculations were based on the assumption that the bubbles blown in mercury leave the outer circumference of the tubes, which is a reasonable assumption since the tube material is not wetted by mercury. Confirmation of the correctness of the assumption is provided by the fact that calculations based on the internal diameters give decidedly low values. On the other hand, when bubbles are blown in a liquid which wets the tube material, the correct value of surface tension is obtained only by calculations based on the inner diameters. The fact that the bubbles form on the inner

TABLE I.—*Diameters of Tubes Used in Surface-Tension Determinations.*

	Silica Tubes.		Glass Tubes.	Stainless-Steel Tubes.
	Set 1.	Set 2.		
	Dia., mm.	Dia., mm.		
Outer tube (external dia.) .	10.93	10.244	7.690	9.597
	±0.05	±0.008	±0.001	±0.015
Outer tube (internal dia.) .	6.73	6.02	5.895	8.084
	±0.01	±0.02	±0.006	±0.070
Inner tube (external dia.) .	2.69	2.702	2.169	2.193
	±0.03	±0.007	±0.013	±0.003
Inner tube (internal dia.) .	1.76	...	1.172	1.479
	±0.01		±0.003	±0.001

surfaces of the tubes can be confirmed visually in the case of water, which wets all the tube material used.

In order to check the reliability of the apparatus, the surface tensions of distilled water and vacuum-distilled mercury were determined. Table II gives the results obtained.

The accepted value for the surface tension of water at 20° C. is 72.8 dynes/cm., with which the average values obtained (73.4 with silica tubes and 72.8 with glass tubes) agree quite well. The average values for the surface tension of mercury obtained with the three types of tubes agree within 1%, averaging 507 dynes/cm. for both nitrogen and hydrogen. Other investigators who have used the maximum-bubble-pressure method have reported values for mercury ranging from 465 to 502 dynes/cm. The values obtained in the present investigation are higher than this range, but are of the same order. It can therefore be concluded that the apparatus and technique are satisfactory.

The silica tubes ground on No. 120 polishing paper are seen to give irregular high values for the surface tension of mercury, while

TABLE II.—*Surface-Tension Determinations on Mercury and Water at Room Temperature (20° C.).*

Liquid.	Tube Material.	Atmosphere.	Abrasive Used in Final Preparation of Ends of Tubes.	Surface Tension, dynes/cm.
Mercury	Silica (Set 1)	Nitrogen	Oakey's No. 120 paper	562
				557
				573
				Aver. 564
Mercury	Silica (Set 1)	Nitrogen	Oakey's No. 400 paper	510
				504
				506
				512
Mercury	Silica (Set 2)	Nitrogen	+5 to -15 μ aloxite on wet polishing cloth	Aver. 508
				510
				509
				510
Mercury	Glass	Nitrogen	Oakey's No. 400 paper	511
				511
				Aver. 510
				513
Mercury	Stainless steel	Nitrogen	Oakey's No. 400 paper	505
				507
				Aver. 508
				502
Mercury	Stainless steel	Hydrogen	Oakey's No. 400 paper	503
				502
				505
				508
Water	Silica (Set 1)	Nitrogen	Oakey's No. 400 paper	Aver. 504
				507
				500
				504
Water	Glass	Nitrogen	Oakey's No. 400 paper	513
				Aver. 506
				73.6
				73.9
Water	Silica (Set 1)	Nitrogen	Oakey's No. 400 paper	73.5
				74.0
				72.7
				72.2
Water	Glass	Nitrogen	Oakey's No. 400 paper	Aver. 73.4
				73.1
				73.2
				71.9
Water	Silica (Set 1)	Nitrogen	Oakey's No. 400 paper	72.4
				73.3
				Aver. 72.8
				72.2

those polished with the two finer abrasives give consistent values of the order expected. These results vary somewhat from those obtained by Bircumshaw,¹ who found that silica tubes, when ground with No. 3 emery, gave values for mercury of the order expected, but when polished with "fine emery", gave much higher values. Using glass tubes, he found that the fine-emery polish gave only slightly higher values than the No. 3-emery finish.

2. Density Determinations.

In determining surface tension by the maximum-bubble-pressure




FIG. 2.—Density Apparatus.

KEY.

- A and B. Silica or stainless-steel tubes sealed into C.
- C. Double-core silica rod adaptable to stand used for surface-tension determinations.
- D. Two-way cock.

a measure of density, since the surface-tension effects cancel out.

The formula used was :

Density of metal =

$$\frac{\text{Pressure difference (cm. water)} \times \text{Density of water at room temp.}}{\text{Vertical distance between the ends of tubes (cm.)}.$$

method, it is necessary to know the density of the molten metal under investigation. The apparatus shown in Fig. 2 was developed for this purpose. The protruding ends of the two tubes were arranged to be 4.5–5.0 cm. apart vertically, and the precise distance was measured by a travelling microscope. The tubes were obtained with identical lower-end diameters by taking a length of tube of 2.5–3.0 mm. external dia., cutting it in the desired position, and polishing the two mating surfaces flat and perpendicular to their axes.

The difference in the pressures required to detach bubbles from the two tubes in turn (measured as in surface-tension determinations) provides a

A small correction has to be made to the measured distance between the ends of the two tubes to allow for the thermal expansion of the tubes and for the increase in depth of immersion caused by the extra metal displaced from inside the deeper-immersed tube as compared with the second tube.

The apparatus was checked by determining the density of mercury at 20° C. The results obtained are given in Table III.

TABLE III.

Pressure Difference, cm. water.	Corrected Length Between Ends of Tubes, cm.	Density, g./c.c.
64.7	4.779	13.54
64.7	...	13.54
64.6	...	13.53

The accepted value for the density of mercury is 13.546 at 20° C., with which the observed values agree closely, proving the method is sound.

III.—EXPERIMENTAL PROCEDURE FOR CADMIUM-ANTIMONY AND LEAD-ANTIMONY ALLOYS.

1. Liquidus Measurements.

Various alloy compositions were chosen to obtain an accurate graph of surface tension plotted against composition, with particular attention to the vicinity of the intermetallic compound in the cadmium-antimony system. Cooling curves were determined on those alloys for which the liquidus temperatures were not accurately known, a portable potentiometer reading to 1° C. being used. Samples of approximately 1000 g. of each alloy were used.

2. Density Measurements.

The metal or alloy was melted, and the stand placed over the furnace and levelled. The ends of the tubes were gradually lowered into the metal, and the pressures required to detach bubbles from the two tubes in turn were measured. This was done for temperatures increasing in 10° C. intervals over a range of 100° C. from the liquidus, except for those cadmium-antimony alloys containing more than 50% antimony. These were found to attack stainless steel severely and silica slightly, and only two points were obtained for them near the liquidus, using silica tubes.

The density values thus obtained were plotted against temperature and the average values used in the surface-tension calculations.

3. *Surface-Tension Measurements.*

Surface-tension measurements were carried out over the ranges of temperature investigated in the density determinations. The values of Macleod's "constant" were calculated for each surface-tension determination.

(a) *Cadmium-Antimony System.*—Nitrogen was found to give inconsistent and high results for the surface tension of cadmium. Hydrogen gave consistent results agreeing closely with published figures of other investigators, and was therefore used throughout all tests on this system.

Uncovered cadmium drossed severely, but a thin layer of molten flux on the metal surface was found to prevent this trouble. Satisfactory fluxes were:

(i) 22% KCl, 78% CdCl_2 , m.p. 383°C .

(ii) 41.5% KBr, 58.5% CdBr_2 , m.p. 302°C .

These fluxes tended to become viscous and finally solid after a few hours (depending on the temperature). The addition of a small amount of ammonium chloride gave a flux which appeared to stay fluid for a longer time and which could be used satisfactorily for one test. Chemical tests failed to reveal any potassium in the metal.

(b) *Lead-Antimony System.*—This system gave more experimental difficulties in surface-tension determinations than the cadmium-antimony alloys because, when the temperature was within approximately 100°C . of the liquidus, the maximum bubble pressures were inconsistent, and this condition became progressively worse as the temperature decreased in this range. The trouble was particularly evident with the lower-antimony alloys (10 and 20% antimony). Values obtained in this doubtful range gave a marked positive gradient, although little reliance can be placed on these figures. The surface tension of a fresh sample of 10%-antimony alloy gave similar results using nitrogen. It is interesting to note that the parent metals gave much more consistent maximum bubble pressures at temperatures near their melting points than did their alloys. This has not been satisfactorily explained. Grosheim-Krisko⁷ has shown that the viscosities of 0-12%-antimonial lead alloys are slightly less than that of lead, from which it would appear that the viscosity of the alloys has nothing to do with the trouble. Bircumshaw¹ reported that he encountered the same trouble with inconsistency of maximum bubble

pressures when working with lead-tin alloys in the lower-temperature range (250°–350° C.), although he has been able to obtain results in this range.

The curve of surface tension plotted against composition was constructed, using values of the surface tensions at 140° C. above the liquidus temperature for each alloy. No flux was needed to prevent oxidizing.

IV.—RESULTS.

The experimental results are given in Tables IV–XI.

TABLE IV.—*Chemical Analysis of the Three Basis Metals.*

Metal.	Impurities, %.
Electrolytic Cadmium.	Zn 0.016, Pb 0.0115, Cu 0.001, Fe 0.002.
Star Antimony.	Pb 0.42, Cu 0.031, Ni 0.005 max., As 0.02 max., Fe 0.005 max.
B.H.A.S. Special Lead.	Ag 0.003, Cu 0.0014, Zn 0.018.

TABLE V.—*Composition-Liquidus Data for the Three Metals and Thirteen Alloys Used.*

Alloy No.	Composition.	Liquidus Temperature, °C.
	Electrolytic cadmium	321°
	Star antimony	630°
	B.H.A.S. special lead	327°
1	18.8% Sb, 81.1% Cd †	343° *
2	29.5% Sb, 70.3% Cd †	379° *
3	40.4% Sb, 59.4% Cd †	432° *
4	48.7% Sb, 51.1% Cd †	452°
5	53.8% Sb, 45.9% Cd †	456°
6	59.0% Sb, 40.7% Cd †	445°
7	71.2% Sb, 28.5% Cd †	505° *
8	87.3% Sb, 12.3% Cd †	569° *
9	10.1% Sb, 89.9% Pb	260°
10	18.6% Sb, 81.1% Pb	313° *
11	38.5% Sb, 61.1% Pb	430° *
12	64.1% Sb, 35.8% Pb	522° *
13	79.7% Sb, 20.2% Pb	577° *

* Values obtained from cooling curves. The remainder were taken from Hansen, "Der Aufbau der Zweistofflegierungen", Berlin: 1936.

† Values obtained by difference.

The surface-tension composition relationships and the phase diagrams of the two alloy systems, as obtained from the experimental results, are given in Fig. 3.




FIG. 3.—Surface-Tension-Composition Relations and Phase Diagrams for: (a) Cadmium - antimony alloys. (b) Lead-antimony alloys.

TABLE VI.—Surface-Tension Values Obtained for Cadmium, Lead, and Antimony.

The values obtained by other investigators (using hydrogen) are given for comparison.

Temp., °C.	Surface Tension, dynes/cm.						Temp., °C.	Surface Tension, dynes/cm.	
	Cadmium.			Lead.				Antimony.	
	Author.	Bircumshaw. ¹	Hogness. ⁸	Author.	Bircumshaw. ¹	Hogness. ⁸		Author.	Bircumshaw. ¹
330°	564	570	635°	383	...
340°	577	...	606	448	640°	384	350
350°	584	583	...	449	453	442	650°	384	...
360°	596	446	675°	384	...
370°	608	592	616	444	700°	382	349
380°	606	...	617	443	725°	383	...
390°	604	442	750°	383	...
400°	609	597	...	443	446	438	775°
410°	600	442	800°	380	346
420°	598	...	622	442
430°	608	441
440°	606	439
450°	611	...	621
460°	608
470°	612
480°	607
490°	599
500°	600	591	619

TABLE IX.—Density, Surface Tension, and Macleod's "Constant" versus Temperature Results for Lead and Alloys 9-11 Inclusive.

Temp., ° C.	Lead.			Alloy 9.				Alloy 10.			Alloy 11.		
	Density (D), g./c.c.	Surface Tension (γ), dynes/cm.	Macleod's "Con- stant", $\gamma^{\frac{1}{2}}/D$.	Surface Tension (γ), dynes/cm.		Macleod's "Con- stant", $\gamma^{\frac{1}{2}}/D$.	Density (D), g./c.c.	Surface Tension (γ), dynes/cm.	Macleod's "Con- stant", $\gamma^{\frac{1}{2}}/D$.	Density (D), g./c.c.	Surface Tension (γ), dynes/cm.	Macleod's "Con- stant", $\gamma^{\frac{1}{2}}/D$.	Density (D), g./c.c.
				Nitrogen.	Hydrogen.								
320°	427?
330°	416?	427?
340°	10.57	448	0.436	417?	428?
350°	10.55	449	0.436	420?	429?	...	9.479
360°	10.54	446	0.437	430?	429?	...	9.464
370°	10.52	444	0.437	429?	432?	...	9.441	436	0.483
380°	10.52	443	0.437	430	432?	...	9.423	434	0.484
390°	10.51	442	0.437	430	437	0.452	9.406	433	0.485
400°	10.49	443	0.438	429	436	0.453	9.385	433	0.485
410°	10.46	442	0.438	429	435	0.453	9.365	432	0.486
420°	10.46	442	0.439	428	434	0.454	9.342	431	0.487
430°	10.43	441	0.439	427	433	0.454	9.324	430	0.487
440°	10.43	439	0.439	429	432	0.455	9.311	428	0.488	8.510
450°	427	431	...	9.287	427	0.489	8.504
460°	424	431	0.455	8.498	410	0.529	...
470°	424	430	0.455	8.493	409	0.530	...
480°	423	430	0.456	8.486	409	0.530	...
490°	421	429	0.456	8.480	408	0.531	...
500°	420	429	0.457	8.470	407	0.531	...
510°	8.467	405	0.531	...
520°	8.462

TABLE X.—*Density, Surface Tension, and Macleod's "Constant" versus Temperature Results for Alloys 12-13 Inclusive and Antimony.*

Alloy 12.				Alloy 13.			Antimony.		
Temp., ° C.	Density (<i>D</i>), g./c.c.	Surface Tension (<i>γ</i>), dynes/ cm.	Macleod's "Con- stant", $\gamma\frac{1}{D}$.	Density (<i>D</i>), g./c.c.	Surface Tension (<i>γ</i>), dynes/ cm.	Macleod's "Con- stant", $\gamma\frac{1}{D}$.	Density (<i>D</i>), g./c.c.	Surface Tension (<i>γ</i>), dynes/ cm.	Macleod's "Con- stant", $\gamma\frac{1}{D}$.
540°	7.729
550°	7.721
560°	7.700
570°	7.670	392	0.580
580°	7.660	392	0.580
590°	7.643	392	0.581	...	395	0.647
600°	7.628	391	0.582	6.880	394	0.647
610°	...	389	0.583	6.875	393	0.647
620°	...	388	0.584	6.858	394	0.647
630°	...	386	0.584	6.851	391	0.647
640°	6.839	391	0.649	...	384	0.678
650°	6.825	389	0.650	6.530	384	0.678
660°	6.820	389	0.651
670°	6.820	389	0.651	6.518	384	0.679
680°	6.815
690°	6.813
700°	6.509	382	0.679
725°	6.498	383	0.681
750°	6.468	383	0.683
775°	6.458
800°	6.424	380	0.687

TABLE XI.—*Average Increase in Macleod's "Constant" for the Various Metals and Alloys Investigated.*

Metal or Alloy.	Temperature Range, ° C.	Average Increase in Macleod's "Constant" per ° C.
Cadmium	330°-390°	0.00040
Cadmium	390°-500°	0.00085
Alloy 1	350°-440°	0.00017
Alloy 2	390°-460°	0.00011
Alloy 3	440°-540°	0.00024
Alloy 4	460°-560°	0.00014
Antimony	635°-800°	0.00006
Lead	340°-440°	0.00003
Alloy 9	390°-500°	0.000045
Alloy 10	370°-450°	0.000075
Alloy 11	460°-510°	0.00004
Alloy 12	570°-630°	0.000075
Alloy 13	590°-670°	0.00005

V.—DISCUSSION OF RESULTS AND CONCLUSIONS.

The surface tension of cadmium has been found to have a large positive temperature coefficient from its melting point upwards for 40°C ., after which it becomes slightly negative. This is in agreement with other workers, including Bircumshaw¹ and Hogness.⁸ The variation of values obtained by different investigators for cadmium and antimony is of the same order as that obtained for mercury.

Macleod's "constant" has been found to increase for all the liquids investigated. If the constancy of this relation is accepted as a criterion of an unassociated liquid, then it appears that all the metals and alloys investigated are associated to some extent in the liquid state for the temperature ranges investigated. It has also been shown that the increase in Macleod's "constant" is much larger for cadmium (330° – 370°C .) and the cadmium-antimony alloys Nos. 1–4, than it is for lead, antimony, cadmium (370° – 500°C .), and the lead-antimony alloys. The ranges of temperature investigated for the cadmium-antimony alloys Nos. 5–8 were not sufficiently large to obtain an accurate average increase in Macleod's "constant", but the values which have been obtained indicate that these alloys give similar results to alloys Nos. 1–4. These results suggest that cadmium (350° – 370°C .) and cadmium-antimony alloys are more highly associated than lead, antimony, cadmium (370° – 500°C .), and lead-antimony alloys. The higher association of cadmium-antimony alloys could be due to the persistence of the intermetallic compound CdSb in the liquid state.

The curves of surface tension plotted against composition show a large fall for the cadmium-antimony system, which contains a solid intermetallic compound, but only a small fall for the lead-antimony system, in which no solid intermetallic compound occurs. From these results it may be concluded that the intermetallic compound (CdSb) existing in solid cadmium-antimony alloys up to the liquidus temperature does not decompose during melting.

The method developed for measuring the densities of molten metals and alloys was found to give reproducible results, the values obtained for mercury, lead, antimony, and cadmium being in close agreement with accepted values.

REFERENCES.

1. L. L. Bircumshaw, *Phil. Mag.*, 1926, [vii], 2, 341; 1927, [vii], 3, 1286; 1928, [vii], 6, 510; 1931, [vii], 12, 596; 1934, [vii], 17, 181.
2. S. Sugden, *J. Chem. Soc.*, 1924, 125, 32, 1167.
3. D. B. Macleod, *Trans. Faraday Soc.*, 1923, 19, 38.

4. Y. Matsuyama, *Sci. Rep. Tohoku Imp. Univ.*, 1927, [i], **16**, 555.
5. F. Sauerwald and G. Drath, *Z. anorg. Chem.*, 1926, **154**, 79; 1927, **162**, 301;
1929, **181**, 353.
6. S. Sugden, *J. Chem. Soc.*, 1922, **121**, 858.
7. K. W. Grosheim-Krisko, *Z. Metallkunde*, 1942, **34**, 102.
8. T. R. Hogness, *J. Amer. Chem. Soc.*, 1921, **43**, 1621.

AUTUMN LECTURE, 1947.

1116

THE METALLURGICAL RESOURCES OF SCOTLAND.

By PROFESSOR G. WESLEY AUSTIN,* O.B.E., M.A., M.Sc.,
VICE-PRESIDENT.

EIGHTEENTH AUTUMN LECTURE TO THE INSTITUTE OF METALS, DELIVERED 23 SEPTEMBER 1947.

SYNOPSIS.

A survey is made of the ores, fluxes, fuels, and hydro-electric energy available, the favourable geographical location, climate, and existing plants. Also, and particularly, the technical and scientific heritage in metallurgy, as exemplified by the invention of the hot blast by Neilson, the steam hammer by Nasmyth, and the varied contributions to the problem of steel quality by McCance, prove great latent capacity.

The material resources, together with the metallurgical inheritance, and latent capacity can assure an interesting future, even during, and after, a possible transition from conventional heavy metallic construction with massive parts, to lighter, often fast-moving apparatus, of greater precision. But design, research, and development, and training in these, should be carried out on a very large scale, hitherto unapproached, to ensure progress, to discover talent, and to distribute and buffer employment. Such design and research and development establishments scattered over Scotland, with full-scale operated pilot plants, could absorb some of the power resources available, and perhaps be more in line with traditional Scottish methods and future requirements than the erection of a few standardized, gigantic metallurgical plants in or near the present industrial zone.

MAY I say at once how greatly I appreciate the honour you have conferred on me by inviting me to deliver the Autumn Lecture. It was not easy to select a suitable subject, and I trust the present title and subject matter are appropriate to this meeting. Perhaps you will decide during and after the lecture that I have not been strictly fair in my treatment of the subject: I felt the word "resources" gave me a chance to develop several themes to which I am particularly attached. For not only do I propose to discuss "resources" in the sense of "supplies"—prolific, as those described by Captain Cook in his first voyage when he opened up the Bay of Plenty, where "the anchor was let go in eleven fathoms, the seine nets were got out and marvellous hauls of fish were made, while the shore parties bought oysters, wild celery, lobsters, wood, and plenty of good water", or scanty, perhaps,

* Professor of Metallurgy, Cambridge University.

as in the passage of Victor Hugo's "Toilers of the Sea" in which the hero, supposedly entirely without resources, had wreckage for fire, water for power, wind for blast, a stone for an anvil, and his will alone for energy, yet successfully completed his task—but I propose to describe also the resource of some Scotsmen, particularly metallurgists, in their capability of meeting a situation or problem, rising to the occasion, and finding a solution. So, perhaps by considering the resources of this country, and the resource of its people, a picture may be obtained of the possibilities of the future.

I should like at this stage to acknowledge the help I have received from many friends, books, and periodicals; to list them all would almost double the length of this lecture.

The mineral deposits of Scotland were dealt with by Dr. Robertson in his lecture to the Scottish Local Section of the Institute in 1945. Most of my comments are taken from Dr. Robertson's paper. He concluded that, on the whole, the Scottish output and resources of most of the common economic minerals are low. Lead and zinc ores have been worked profitably, and although not worked at present, there is a possibility of profitable deposits at greater depths. Copper and nickel occur in small amounts, but it seems doubtful whether exploitation will occur. The principal iron ore is a Scottish black-band. Clay-band has also been worked. The estimated resources of the black-band ores of Scotland are :

Proved	7,772,000 tons.
Probable	76,652,600 tons.
Possible	423,230,500 tons.

Mushet discovered this stone in 1801 when crossing the Calder in the parish of Old Monkland. He quickly satisfied himself of its nature, iron content, and value. It was smelted at once at the Calder Iron Works and the Clyde Iron Works. But it was not extensively used until 1825 when, in addition, raw pit coal and hot blast were employed. Mushet considered the hot blast admirably adapted for smelting black-band iron-stone. The output per furnace increased from 60 to 90 tons per week, of which 10 tons were attributed to the use of pit coal and 20 tons to hot blast. There were then some 33 furnaces in the neighbourhood of Glasgow smelting black-band. The bed of oolitic iron-stone in the south of the Isle of Rasay should also be mentioned.

Fluxes and refractory materials are more plentiful. Limestones have been extensively worked; there are immense quantities of high-grade dolomite in the North-West Highlands. There are also large and very valuable resources of fire-clays. Silica in various forms and

purities is available and may be potentially very valuable. The fineness of the sea sand is remarkable; consider the sands of Iona trodden by St. Columba.

Turning next to sources of energy, Scotland possesses immense coal reserves, estimated at 21,000 million tons. The majority of the coals are bituminous: but there are first-class steam coals, bunker coals, house coals, gas and cooking coals, and anthracitic types. Quantity, quality, and variety are thus available for metallurgical purposes.

Dr. James Young of Glasgow obtained a patent in 1850 for the distillation of bituminous coals to obtain paraffin wax and oils. But Young turned from the coals to bituminous shales, and the successful results of his investigations led to the Scottish shale-oil industry. The Scottish shale-oil industry is the only one which has been developed on a large scale. The production of oil from shale is about 21 gal. per ton. Ordinarily, oil from an oil-field is cheaper, but the plants developed in Scotland for refining shale oil became examples for the oil-fields of the rest of the world.

The water-power resources of Scotland are now being developed by the North of Scotland Hydro-Electric Board. It is expected that the production of electricity will reach 400,000 kW. within the next three years and that this will increase as time goes on. This is a large output of power. Some 3000 million units per annum will be available for new industrial or agricultural purposes.

The foregoing brief review has indicated a country rich in fuels, electrical energy, and refractory materials, but poor in ores, except black-band iron-stone. The excellent geographical location, with its indented coast-line, on the fringe of the great western land mass, suggests the importation of ores, bringing them to the fuels and energy. This is, of course, occurring, and exemplary plants for iron and steel production, with manifold products, for aluminium production, and for the forming of many metals and alloys by a wide variety of processes, are in operation. Many of the plants will be visited by members.

Next, let us consider the resource which Scotsmen have applied to typical metallurgical problems. First, that of James Beaumont Neilson, who was born in Shettleston in 1792. He became foreman and then manager of the Glasgow Gas Company. In the course of his employment he made many improvements to the gas-generating plant and to the gas-consuming apparatus. Apparently, a Glasgow iron-master asked his advice whether it were possible to purify the air blown into the blast furnaces in the same way as coal gas is purified. The iron-master thought that the presence of sulphur in the atmospheric air caused the irregular working and poorer iron obtained during the

summer months. Neilson, however, thought over the matter, and in a paper read in 1825 stated, correctly, that the cause was a want of oxygen during the summer months on account of the lower density of the air and also because of the greater moisture content in the air in the summer. His idea to deal with the latter was to pass the air through two long tunnels containing calcined lime and so dry the air. He did not actually test this idea. He was also asked advice from a friend about an iron furnace situated half a mile from the blowing engine, and which did not make as much iron as a furnace located nearer. It occurred to Neilson that if the air at the distant furnace were heated, and its volume increased, it might do more duty. Being an experimentalist, he at once tried the effect of heated air on the combustion of illuminating gas, and observed more perfect combustion, and that the illuminating power of the flame had increased. He repeated the experiment in a smith's fire, and noticed that the heat was more intense. He considered that a similar increase in the intensity of combustion, and in temperature, would occur if the same plan were applied on a much larger scale to the blast furnace. The iron-masters were not prepared to listen to his proposals because their own observations led them to believe that the colder the blast the better the quality of the iron made, and the larger the quantity. But as an early writer on the subject very properly stated " . . . this being the state of the practice, and this the state of the science, and known to men of skill in the iron trade, it occurred to Mr. Neilson, who was fortunately out of the trade, and consequently unencumbered with either its practices or its prejudices, that the power of the blast in igniting the materials would be greatly increased if in its passage to the tuyères it were heated to a very considerable temperature". Neilson, in his experiments, had glimpsed the factor of intensity. He at length obtained permission from Mr. Charles MacIntosh and Mr. Colin Dunlop of the Clyde Iron Works to try out the effect of blowing the heated air into an iron furnace. The results soon showed that the idea was sound, and although the design and development of a successful stove proved difficult, success eventually followed. The difficulties were concerned with the design and operation of apparatus and not with the principle. The total coal consumption eventually fell from about 8 tons per ton of iron made with cold blast to 5 tons per ton of iron made with the blast heated to 150° C.

Neilson's invention thus resulted in a considerable saving of fuel, and in increased output. Both these factors are of great importance to metallurgists at the present time. It is permissible to speculate whether further development along the lines of Neilson's invention are possible to-day. I think so. A similar increase in the intensity of combustion

may be obtained by removing the nitrogen ballast from the air supplied to furnaces, notably the blast furnace and the open-hearth steel furnace. The condition is that described by Neilson, namely, input of heat at a high temperature level. The application of such enriched airs, or oxygen, could prove very successful. Examples might be the production of ferro-alloys in small blast furnaces, and much more rapid melting in the steel furnaces. The application might also give rise to increased output from a given apparatus, and lower fuel consumption. The field of fuel economy in metallurgical works is to-day most important.

I would refer next to the invention of the steam hammer by Nasmyth. Time is inadequate to deal with the fascinating history of the family, whose coat of arms was a sword between two hammers with broken shafts and the motto "Non arte sed Marte". James Nasmyth eventually proved himself a true smith despite the family coat of arms and motto. He was born in Edinburgh in 1808, and from the age of 15 onwards made excellent working models of steam engines which he sold, and used the proceeds to pay for admission to the lectures on Natural Philosophy and Chemistry delivered at the University of Edinburgh. He also made an engine for a steam coach, which worked successfully and was eventually employed to drive a small factory. He determined to work in a large engineering works, and decided that the factory of Henry Maudslay of London was the most desirable. He made, including the castings and forgings, a small steam engine which he took and showed Maudslay, who at once appointed him as his private mechanic. We obtain a glimpse of a true mechanical engineer, capable of using tools and of producing sound designs. He founded the Bridgwater Foundry in Manchester, where he invented the steam hammer.

The tools for working iron had not kept pace with the production of the metal, and although improvements had been made to tilt hammers, they were capable of working only small sections. Machine tools were being made in Nasmyth's factory to machine the engines of a large paddle steamer, and the problem arose of forging the large 30-in. dia. paddle shaft for the vessel. No forge-master was prepared to undertake this work, and the designer asked Nasmyth if he might dare to use cast iron. Nasmyth immediately considered the mechanics of the existing hammers, and then stated the problem to himself, which was that of lifting a block of iron sufficiently high, letting it fall on to the forging, and guiding it while it fell. He made a sketch immediately of a steam-lifted block to carry out the programme of operations he had conceived, and the steam hammer was invented. The paddle shaft, however, was not forged because screw propulsion was substituted

in the vessel. No forge-master was prepared to order a hammer, particularly in view of the then prevailing depression, perhaps not realizing that a new tool, enabling new products to be made, might conceivably help to break the depression. The French iron-master, Schneider, of le Creusot, when on a visit to Nasmyth's works, in Nasmyth's absence was shown the sketches of the hammer, and on his return to France built a hammer on these principles. Nasmyth later, when on a visit to le Creusot, saw his invention at work there. On his return to England, a hammer was soon built. It worked successfully, as was expected, and full development followed.

The steam hammer was invented to meet a particular technical problem, the forming of a mass of metal into a desired shape. It involved a considerable knowledge of mechanics and an unusual capacity in mechanical design. Nasmyth's father was an exceptionally gifted artist and had a good knowledge of architecture and civil engineering. These factors may have led to the son's interest, and success, in design.

The design and manufacture of plant for forming metals and alloys is of the greatest importance in metallurgy. The behaviour of metals subjected to deformation, cold and hot, is a subject now fairly well understood; but much remains to be done to design the most efficient machines for carrying out forming operations on all sizes of material. Surely the mechanical skill employed in the design of ships, their parts, and their power plants can be applied to this problem? The hammer, the press, and the mill still offer many problems which await inspired and detailed design. Other forming processes, casting, welding, and compacting, present their problems, but these are preponderantly of a scientific nature.

May I now be permitted to pass to a problem of a very different type? I refer to the "quality" of steel. The question, as it then appeared, was stated in Glasgow on several occasions by Mushet over a century ago. May I quote his words? "At this day, assisted by a variety of facts, mechanical and philosophic, we yet remain in comparative ignorance of what constitutes the real difference in point of quality betwixt home-made iron and that imported from foreign markets" . . . "but if the matter is impartially investigated, there will be sufficient reason to comprehend that our knowledge and general progress in the iron trade are more applicable to quantity than quality. The successful exertions of individuals have increased the manufacture of cast and malleable iron beyond all precedent in this country."

Although the question has become modified during the century, it was constantly asked wherein lay the real difference between steels of the same general composition, made by different processes, at different

works? These differences were revealed by their relative ductility, toughness, ability to case-harden, hardenability, &c.

Dissolved gases were considered a possible cause, and the gases evolved on heating steels were investigated for quantity and composition by very many workers, the late Dr. J. W. Donaldson among them. It was found that with increasing temperature of extraction the proportion of carbon monoxide increased. New techniques, such as adding tin and antimony, and the use of high-frequency heating permitted fusion, and a further increase in carbon monoxide was observed. The conclusion was then slowly reached that the carbon monoxide was a reaction gas, not a gas held in solution, and that it was generated by the reduction of iron and other oxides in the steel by the carbon present. These hot-extraction methods were thus not really methods for the determination of dissolved gas, but for the determination of oxide in steel. Progress was also made with wet-extraction methods, and a clearer picture was obtained of the quantity and composition of the solid oxides present. Inclusions in steel were also investigated by various methods, particularly metallographic, and the paper by McCance on "Inclusions in Steel" in 1918 focused attention on this aspect of the subject.

A further very important development was the attempt made by McCance shortly afterwards to apply the laws of physical chemistry to steel and steel-making processes. His theoretical treatment of the solubility of oxygen in molten iron broke new ground and was one of the starting points for a series of very fruitful researches and one can say a whole literature on this very important subject, which, while absorbing theoretical interest, is now able to deal quantitatively with many of the actual operating aspects of steel production. The origin, type, and composition of inclusions or slags—"every impurity which enters into a metal from the melting vessel"—were now becoming more clear.

But, further, the original pattern of the inclusions in the ingot of steel as cast, its skeletal form, was also being brought out, together with the features of ingot segregation, by groups of investigators. Service has made important contributions in this field. It was demonstrated clearly that the dendrites growing inwardly into the mother liquor both push forward some slag inclusions and enmesh or "land-lock" others, so mapping out both a major ingot pattern and a minor interdendritic one in which a skin of inclusions surrounds the dendritic forms. The grosser heterogeneities of pipe, A- and V-segregates, and the sedimentary cone were also explained. These gross macro- and finer micro-patterns persist throughout the normal life of the steel. They are deformed and

perhaps broken up by the working processes, but nevertheless they finally give rise to the texture or fibre of the finished product. The bold relief, or fineness, of this pattern has a great effect on the quality of the steel, particularly as measured by tests "with" or "across" the grain; in fact, many of the old differences of quality can now be adequately explained. The theory also indicates directions in which quality may be improved, and sets limits to the quality which may be expected from large masses of metal produced by present-day processes.

What lines of development may be expected in this field? Certainly a great improvement in the quality and uniformity of our products as knowledge now available is persistently applied to practice. Research work in progress on the effect of gases on quality has already given very important results and will doubtless give more. It may prove, however, that avoidance altogether of the ingot stage of metal making is the only method of avoiding grosser heterogeneities. The continuous solidification of a jet of molten metal may be the answer.

Light has thus been thrown on the old question of the quality of steel, mainly by groups of workers, investigators in quite different fields, although definite moves forward and indications of promising lines have been made by particularly gifted workers here and elsewhere. Rather than the individual inspiration to "heat the blast" or "lift the hammer by steam", the teams, inspired by intellectual curiosity or pressure of urgent works problems, have together solved the problem. Here, as elsewhere, if the problem be compared with a forest, the greater the area cleared, the more numerous are the contacts with the remaining trees. This is perhaps in accordance with the nature of a complex problem, and to-day such problems seem to be the principal ones.

Trained scientists and technologists are more than ever necessary for the solution of such problems. Scotland's share in the training of metallurgists is large, and its graduates have proved successful in all fields. If I might be permitted, I would suggest that somewhere instruction, and facilities for research, in technical electrometallurgical processes and metallurgical engineering be provided, particularly in view of the hydro-electric developments to which I have referred. It would be particularly appropriate there, for the students would see at first hand the importance of electrometallurgical processes.

Do these sketches I have attempted to make of the material resources, location, heritage, emergence of gifted men, and flow of metallurgists enable us to suggest a line, or lines, or development? I think they do. It is possible that a gradual transition is occurring in our large-scale employment of metals and alloys as constructional materials. Reasons of economy alone compel us to construct as lightly as possible;

with lighter and smaller power units the majority of transport will tend to decrease in size and become faster in movement. Perhaps the day of the great ship and the heavy train is passing. During such a period, design, research, and development should be extremely active if a position in the van of progress is to be maintained. The numbers engaged on these problems should be increased. With every increase in numbers, there is a greater possibility of discovering first-class talent.

Several problems awaiting solution have already been indicated, and there remains the great problem of the gasification of coal underground. This surely is one requiring knowledge of many branches of physics, chemistry, and engineering. Much of the data required for the solution is already known. Much more could be obtained by team work. The large-scale experimental work would demand first-class engineers and chemists. With the will and the investigators, the problem cannot be regarded as without prospects of solution.

The trend seems, therefore, towards a very large-scale expansion of research and development, directed towards the main problems of fuel supply and economy, metal extraction, forming processes, and the application of metals and alloys.

Superb locations are available in Scotland for such establishments, and ample power to operate large trial plants is becoming available. Some of the establishments could be located in development areas, and others in the Highland centres. They would absorb man-power, act as foci for instruction, and complement other schemes for a wider dispersal of flexible activities throughout Scotland. Such schemes, or modifications of them, might be more capable of rapid realization, and of greater value to our economy, than the erection of a few giant metallurgical plants in or near the present industrial zone.

